



दि न्यू इन्डिया एश्योरन्स कंपनी लिमिटेड, मुंबई (प्र.का.)  
THE NEW INDIA ASSURANCE CO. LTD. MUMBAI (H.O.)

### TENDER NOTICE

**Date: 09/10/2023**

**Tender No:- 18Retnd/Est&Estb/Giriraj/ 2023-24**

**Re:-Tender for structural repair works at flat 7E Giriraj CHS, Altamount Road, Mumbai- 400026**

Tenders are invited in 2 bid system (Technical and Price bids) for appointment of a contractor to carry out the structural repair works at flat 7E Giriraj CHS, Altamount Road, Mumbai 400026.

The work shall be executed as per specifications & Supervision of the architect, M/s Architects Approach.

Tender documents can either be downloaded from company's E-procurement portal  
[www.tenderwizard.com/NIAEPROC](http://www.tenderwizard.com/NIAEPROC) or [www.newindia.co.in](http://www.newindia.co.in)

*The cost of tender is Rs. 590/- (inclusive of GST) (non-refundable) to be paid by DD favoring The New India Assurance Co. Ltd. payable at Mumbai on or before the last date of submission at the office Estate Department, Head Office. EMD for this work is Rs. 10000/- (without interest) to be paid by DD favoring The New India Assurance Co. Ltd. payable at Mumbai on or before the last submission at the office of Chief Manager, Estate Department, Head Office. Scanned copy of same (tender fee DD and EMD DD) must also be uploaded on the website [www.tenderwizard.com/NIAEPROC](http://www.tenderwizard.com/NIAEPROC). MSE (Micro and Small Enterprise) registered firms are exempted from paying the tender cost and EMD on submission of valid certificate and the MSE certificate shall be uploaded on portal and hard copy of MSE certificate to be submitted to HO.*

The estimated cost of the project is Rs. 44 Lacs.

**PRE BID MEETING AT SITE -19-10-2023 (11:00AM)**


Bidders can submit their bid on or before 30th October 2023 up to 03:00 PM through e-procurement only i.e., through [www.tenderwizard.com/NIAEPROC](http://www.tenderwizard.com/NIAEPROC). No other mode of bid submission is accepted

The New India Assurance Company Ltd do not bind themselves to accept any or all bids and reserves the right to accept any or all bids without assigning reason.

*The successful bidder after finalization of the tendering process must note that the society does not permit execution of work on Sundays/Public Holidays.*

**Note:- No documents except tender fee and EMD DD and MSME certificate to be submitted offline.**

**[MSME certificate should be of Civil Repair Works ]**

  
Chief Manager  
Estate and Establishment Department

### **INDEX**

<b>SR. NO.</b>	<b>DESCRIPTION</b>	<b>PAGE NO</b>
1	TENDER NOTICE	1
2	SPECIAL INSTRUCTIONS TO BIDDERS FOR E-TENDERING	03-04
3	MOST IMPORTANT INFORMATION	05
4	INSTRUCTION FOR FILLING THE TENDER	06-08
5	GENERAL CONDITIONS	09– 28
6	SPECIAL CONDITION OF CONTRACT	29– 30
7	SCHEDULE 'F'	31– 32
8	GENERAL SPECIFICATION	33 – 36
9	LIST OF INDIAN STANDARDS	37– 39
10	LIST OF MATERIAL OF APPROVED BRAND & MANUFACTURER	40 –43
11	ANNEXURE 1-TECHNICAL BID	44
12	ANNEXURE-2- SECURITY DEPOSIT	45
13	ANNEXURE-3- PRICE BID (BILL OF QUANTITY)	46-60

### **SPECIAL INSTRUCTIONS TO BIDDERS FOR E-TENDERING**

1. Tender document with detailed terms and conditions is available on our Website [www.tenderwizard.com/NIAEPROC](http://www.tenderwizard.com/NIAEPROC). Interested parties may download the same and participate in the tender as per the instructions given therein, on or before the due date of the tender. The tender shall have to be submitted online through the e-Procurement system on [www.tenderwizard.com/NIAEPROC](http://www.tenderwizard.com/NIAEPROC).
2. As a pre-requisite for participation in the tender, vendors are required to obtain a valid Digital Certificate of Class IIB (with both signing and encryption component) and above as per Indian IT Act from the licensed Certifying Authorities (For ex. N-codes, Sify, E-mudra etc.) operating under the Root Certifying Authority of India (RCIA), Controller of Certifying Authorities (CCA). The cost of obtaining the digital certificate shall be borne by the vendor. In case any vendor so desires, he may contact our e-Procurement service provider M/s. Antares Systems, for obtaining the Digital Signature Certificate.
3. Corrigendum / amendment, if any, shall be notified on the site [www.tenderwizard.com/NIAEPROC](http://www.tenderwizard.com/NIAEPROC). In case any corrigendum / amendment is issued after the submission of the bid, then such vendors, who have submitted their bids, shall be intimated about the corrigendum/amendment by a system-generated email (In case of open tender corrigendum / amendment will be on the public dash board and no mail will be fired for the vendor who has not participated by that time). It shall be assumed that the information contained therein has been taken into account by the vendor. They have the choice of making changes in their bid before the due date and time.
4. Vendors are required to complete the entire process online on or before the due date of closing of the tender.
5. The Commercial/Price bid of only those vendors shall be opened whose Technical bid is found to be acceptable to us. The schedule for opening the price bid shall be advised separately.
6. Directions for submitting online offers, electronically, against e-Procurement tenders directly through internet:
  - i. Vendors are advised to log on to the website [www.tenderwizard.com/EPROC](http://www.tenderwizard.com/EPROC) and arrange to register themselves at the earliest.
  - ii. The system time (IST) that will be displayed on e-Procurement web page shall be the time considered for determining the expiry of due date and time of the tender and no other time shall be taken into consideration.
  - iii. Vendors are advised in their own interest to ensure that their bids are submitted in e-Procurement system well before the closing date and time of bid. If the vendor intends to change/revise the bid already entered, he may do so any number of times till the due date and time of submission deadline. However, no bid can be modified after the deadline for submission of bids.
  - iv. Once the entire process of submission of online bid is complete, the vendors are required to go to option own bid view through dashboard and take the print of the envelope receipt as a proof of submitted bid.
  - v. Bids / Offers shall not be permitted in e-Procurement system after the due date / time of tender. Hence, no bid can be submitted after the due date and time of submission has elapsed.
  - vi. No manual bids / offers along with electronic bids / offers shall be permitted.
7. Once the Commercial/Price bids are opened, vendors can see the rates quoted by all the participating bidders by logging on to the portal under their user ID and password and clicking on other bid view.

8. No responsibility will be taken by and/or the e-Procurement service provider for any delay due to connectivity and availability of website. They shall not have any liability to vendors for any interruption or delay in access to the site irrespective of the cause. It is advisable that vendors who are not well conversant with e-tendering procedures, start filling up the tenders much before the due date /time so that there is sufficient time available with him/her to acquaint with all the steps and seek help if they so require. Even for those who are conversant with this type of e-tendering, it is suggested to complete all the activities ahead of time. It should be noted that the individual bid becomes viewable only after the opening of the bid on/after the due date and time. Please be reassured that your bid will be viewable only to you and nobody else till the due date/ time of the tender opening. The non-availability of viewing before due date and time is true for e-tendering service provider as well as New India Assurance officials.
9. New India Assurance and/or the e-Procurement service provider shall not be responsible for any direct or indirect loss or damages and or consequential damages, arising out of the bidding process including but not limited to systems problems, inability to use the system, loss of electronic information etc.
10. Bidder should arrange for the Tender Cost/EMD as specified in the tender. The original should be posted/couriered/given in person to the Tender Inviting Authority, within the bid submission date and time of the tender.
11. The bidder has to submit the tender document(s) online well in advance before the prescribed time to avoid any delay or problem during the bid submission process.
12. The details of the Tender Cost and EMD document submitted physically to the Department before due date of submission of tender and the scanned copies furnished at the time of bid submission online **should be the same** otherwise the Tender will be summarily rejected. Ensure that the copies of Tender Cost and EMD are submitted under their respective heads only.
13. The Tender Inviting Authority (TIA) will not be held responsible for any sort of delay or the difficulties faced during the submission of bids online by the bidders due to local issues.
14. Bidder should take into account all the corrigenda published before submitting the bids online.
15. The bidder should see that the bid documents submitted should be free from virus/ and if the documents could not be opened, due to virus, during tender opening, the bid is liable to be rejected
16. Please note that if rates are not filled in BOQ, then system will show it as zero. *If bidder fails to quote any rates in the BOQ, then their bid will be considered 'incomplete bid' and their bid will be rejected.* Only complete bids will be considered for further evaluation.
17. Tender cost/exemption will be as per government rules applicable to MSME. Please submit relevant certificates in respective heads along with hard copies of the documents in the department for pre-verification.
18. Only bids submitted through online mode will be considered for evaluation.
19. If the amount quoted by the L1 bidder is less than 25% of the estimated cost, she/he shall submit a bank guarantee of amount equal to the difference in the amount quoted and total estimated cost. In case of freak rates for particular items, the L1 bidder shall submit a bank guarantee equal to the difference between the amount quoted and the estimated rate of particular items.
20. In case of any clarification pertaining to e-Procurement process, the vendor may contact the following agencies /personnel:

S.N	Particulars	Company Name	Contact Details
1	FOR e-Tendering Support	M/s. Antares Systems	09923972175 (Mr. Sushant) <a href="mailto:lokesh.hr@etenderwizard.com">lokesh.hr@etenderwizard.com</a>
2	For Tender related Queries	The New India Assurance Co. Ltd	<a href="tel:022-22708514/511">022-22708514/511</a> <a href="mailto:adarsh.kumar1@newindia.co.in">adarsh.kumar1@newindia.co.in</a> <a href="mailto:gaurav.40232@newindia.co.in">gaurav.40232@newindia.co.in</a>

### **MOST IMPORTANT INFORMATION**

Reference No 18/ <u>Est.&amp;Estb./Giriraj/2023-24</u>	
<b><u>Tender for structural repair works at flat 7E Giriraj CHS, Altamount Road, Mumbai- 400026</u></b>	
Tender publishing date	09/10/2023 (9 <sup>th</sup> Oct 2023)
Last Date of Bid submission	30/10/2023 before 03.00 PM
Tender Fees(Non- Refundable)	Rs. 590 /- ( <b>inclusive</b> of 18% GST)
EMD (refundable)	10,000/-
Address for communication and submission of EMD and Tender fees.	Chief Manager, Estate Department, 6 <sup>th</sup> Floor, The New India Assurance Co. Ltd., Head Office, New India Assurance Building, 87, M G Road, Fort, Mumbai – 400 001
Contact Details	Telephone: <b>022-22708514/511</b> E-Procurement portal: <a href="http://www.etenderwizard.com/NIAEPROC">www.etenderwizard.com/NIAEPROC</a> or <a href="https://www.newindia.co.in/portal/TenderNotice">https://www.newindia.co.in/portal/TenderNotice</a>
Architect	<b>M/s Architects Approach</b> <b>Contact no. 9820158656</b>

## **INSTRUCTION FOR FILLING IN TENDER**

### **1.0 THE TENDER OFFER:**

- 1.1 The tender documents will be available on [www.tenderwizard.com/NIAEPROC](http://www.tenderwizard.com/NIAEPROC) as well as [www.newindia.co.in](http://www.newindia.co.in)
- 1.2 **The bidder has to use the E-Tender portal only** for participating in the tender (Refer **SPECIAL INSTRUCTIONS TO BIDDERS FOR E-TENDERING**).
- 1.3 Downloading of tender document from E-Tender portal is mandatory for tender participation.
- 1.4 The online bids under two bid systems comprising of (1) The Technical Bid and (2) Commercial Bid should be submitted online on E-Tender portal on or before **30/10/2023 before 3.00 PM**. The commercial Bill should be quoted **excluding GST & other Taxes (if any) which shall be payable by NIA as actuals.** The various documents to be submitted Online and Offline along with the Technical and the Commercial Bid are motioned in the Section II and Annexure-1 of this document.
- 1.5 **No Offline documents shall be accepted except of tender cost and EMD DD/MSE certificate.**
- 1.6 At any time prior to the last date of receipt of bids, the Company may, for any reason, whether at its own initiative or in response to clarifications requested by the prospective bidders, modify the tender documents by clarifications.
- 1.7 The clarifications, if any, issued by the Company at any time before the due date of submission of the bid will become part of the tender document and would be notified on both the websites.
- 1.8 No bid will be accepted after the due date & time.
- 1.9 The details of the Tender Cost/ Bid Security Declaration document submitted physically to the Department before due date of submission of tender and the scanned copies furnished at the time of bid submission online should be the same otherwise the Tender will be summarily rejected. Ensure that the copies of Tender Cost/Bid Security Declaration are submitted under their respective heads only

## **SECTION – II**

### **PART A-TECHNICAL BID (ONLINE)**

The scanned copies of the following documents

1) **Demand Draft** for Tender Document Fees worth Rs. 590/- (inclusive of 18% GST) towards Tender Fee drawn in favour of “The New India Assurance Co., Ltd.,” payable at Mumbai.

2) **EMD of Rs 10,000 /- (in form of Demand Draft/Fixed Deposit Receipt/Bank Guarantee/e-Bank Guarantee, insurance surety Bond)**

a). Technical Bid as per **Annexure-1** and supporting documents.

### **PART A-TECHNICAL BID (OFF LINE)**

The following documents

- a. Original DD towards tender document Fees
- b. Original Bid Security Declaration

are required to be submitted offline in physical/hard copies to The Chief Manager, Estate Department, The New India Assurance Co., Ltd., Head Office, New India Assurance Building, 87, M G Road, Fort, Mumbai – 400 001 by on or before **30/10/2023 before 3.00 PM** in one sealed envelope super scribed as **Offline Document Submission for “Tender for structural repair works at flat 7E Giriraj CHS, Altamount Road, Mumbai- 400026”** failing which the bidder(s)is/are liable to be rejected and their tender may not be opened.

The details of the DD/any other accepted instrument, physically sent, should tally with the details available in the scanned copy and the data entered during submission time. Otherwise the submitted bid will not be acceptable.

### **PART B-COMMERCIAL BID (ON LINE ONLY)**

- a) Commercial Bid as per **Annexure-3**

**Note: No offline documents are required to be submitted for commercial bid.**

### **SECTION III**

#### **GENERAL TERMS & CONDITIONS**

##### **1. PROCEDURE FOR PROCESSING THE TENDER DOCUMENTS:**

- 1.1 The Committee constituted by the Company will open the “Technical Bid” electronically and off-line documents cover physically. In case, offline documents sealed cover does not contain Demand Draft towards Earnest Money Deposit and Tender documents fees, the bid offer may be rejected.
- 1.2 The Commercial Bids of Technically qualified bidders will be opened by the Committee electronically in the presence of the bidders who wish to be present for opening, L1 will be identified on the Total Price of the Commercial Bid & Summary.
- 1.3 Any Commercial Bid incomplete in any respect will be disqualified.
- 1.4 This procedure is subject to changes, if any, and the procedure adopted by the Company for opening the tender shall be final and binding on all the parties.

##### **2. Location:**

- 2.1 Address of the Premises: **Flat 7E, GIRIRAJ CHS, ALTAMOUNT ROAD, MUMBAI**
- 2.2 Tenderers must get acquainted with the proposed work and study drawings, designs, specifications, conditions of contract and other conditions carefully before tendering. The Tenderer shall seek clarifications on any item, if required, prior to submitting his tender. No request of any change in rates or conditions for want of information on any particular point shall be entertained after receipt of the tenders.
- 2.3 The Tenderer is advised to inspect the site to ascertain the nature of site, access thereto, location, facilities for procurement of materials, labour rates and execution of the work. The Tenderer shall be deemed to have full knowledge of the site and drawings whether or not he actually inspects them.

##### **2.0 AGREEMENT:**

The successful bidder shall have to enter into a detailed Agreement. A Performa/Draft Agreement as mentioned in **Annexure-2**. However, the Company reserves the right to alter/vary/amend/modify all or any of the terms set out in the said Performa/Draft Agreement.

##### **Encl:**

**Annexure-1(Technical Bid)**

**Annexure-2- (Security Deposit)**

**Annexure-3 - (Commercial Bid)**



## **GENERAL CONDITIONS**

Contractor will not disclose details of the work to any person or persons except those engaged in its performance, and only to the extent required for the particular portion.

Contractor will not give any item concerning details of the work to the press or a news disseminating agency without prior written approval from NIA / Architect contractor shall not take any pictures / photographs on site without written approval of NIA /Architect.

### **A. DEFINITIONS:**

1. The “**CONTRACT**” means the documents forming the tender and acceptance thereof any the formal agreement executed between NIA and the Contractor together with the documents referred to therein including these conditions, the specifications bills of quantities, designs, drawings and instructions issued from time to time by NIA or any person authorized by the competent Authority, and all these documents taken together shall be deemed to form one contract and shall be complementary to one another.
2. In the contract the following expressions shall unless the context otherwise required, have the meanings hereby respectively assigned to them.
3. The expressions “**Works**” or “**Work**” shall unless there be something either in the subject or context repugnant to such construction, be constructed and taken to mean the works by or by virtue of the contract contracted to the executed whether temporary or permanent and whether original, altered, substituted or additional.
4. The “**Contractor**” shall mean the individual or firm or company whether incorporated or not undertaking the works and shall include the legal personal representative of such individual or the persons composing such firms or company and the permitted assigns of such individual or firm or firms or company.
5. The “**Contract Sum**” shall mean in case of item rate contracts, the cost of the works arrived at after extension of the quantities shown in the schedule of quantities by the items rates quoted by the Contractor / Tenderer for the various items.
6. A “**Day**” shall mean a day of 24 hours from midnight to midnight irrespective of the number of hours worked on that day.
7. “**Expected risks**” are risks due to riots (otherwise than among Contractor’s labors / employees) and civil commotions (in so far as both these are uninsurable), wars (whether declared or not), invasions, act of foreign enemies, Hostilities, Civil war, rebellion, insurrection military or usurped power, any act of Governments, damage from aircraft, acts of God such as earthquake, lightning and unprecedented floods, and other causes over which the contractor has no control and accepted as such by NIA of the part of works in respect of which a certificate of completions has been issued.
8. “**Market-Rate**” shall be the rate as decided by Architects on the basis of the cost of materials and labour at site when the work is to be executed plus the percentage mentioned in **Schedule ‘F’** to cover all overheads and profits. This is applicable to Extra items.
9. “**Schedule**” referred to in these conditions shall mean the relevant schedule (s) annexed to the Tender documents / papers issued by NIA of the standard schedule of rates prescribed by NIA and the amendments thereto issued from time to time.
10. “**Project Architect**” shall mean **M/s. Architect Approach** and will include duly authorised representative or any other person empowered by them in this behalf to discharge all or any of their functions.
11. **Architect** shall mean qualified Engineer or nominated official (Authorised official) duly appointed by NIA / Architect who will act on their behalf.

12. The competent authority shall mean The **Chief Manager**, Estate Department, The New India Assurance Co. Ltd., Head Office and will include duly authorised representative / officials or any other person empowered by NIA / Architect in this behalf to discharge all or any of their functions.
13. Where the context so requires words imparting the singular only include the plural and vice-versa.
14. Headings and marginal notes to these conditions shall not be deemed to form part thereof or be taken into consideration in the interpretations or constructions thereof of the Contract.
15. **Foreclosure of Contract** in full or in part due to Abandonment or Reduction in scope of work:

If at any time after acceptance of the Tender NIA shall decide to abandon or reduce the scope of the works for any reason whatsoever and hence not require the whole or any part of the works to be carried out, the Architect / NIA (Authorised official) shall give notice in writing to the effect to the contractor and the contractor shall have no claim to any payment of compensations or other issues whatsoever, on account of any profit or advantage which he might have derived from the execution of the works in full but which he did not derive in consequence of the foreclosure of the whole or part of the works.

#### **B. TERMINATIONS OF CONTRACT FOR DEATH:**

1. If the Contractor is an individual or a proprietary concern and the individual or the proprietor dies and if the Contractor is a partnership concern and one of the partner dies then unless the Competent Authority is satisfied that the legal representative of the individual contractor or of the proprietor of the concern and in the case of partnership, the running partners are capable of carrying out and completing the contract, the Competent Authority shall be entitled to cancel the contract / terminate the contract as to liable for payment of any compensations to the estate of the deceased Contractor and / or to the surviving partners of the Contractor's firm on account of the cancellations of the contract. The decision of the competent Authority that the legal representatives of the deceased Contractor or the surviving partner of the Contractor's firm cannot carry out and complete the contract shall be final and binding on the parties. In the event of such cancellation NIA shall not hold the estate of the deceased Contractor and / or the surviving partners of the Contractor's firm liable in damages for not completing the contract.

#### **C. CANCELLATIONS OF CONTRACT IN FULL OR PART:**

If the Contractor

- 1) At any time makes default in proceeding with the work with due diligence and continues to do so after a notice in writing within 7 days from the NIA/Architect/Authorised Official.
- 2) Commits default in complying with any of the terms and conditions of the contract and does not remedy it or take effective steps to remedy it within 7 days after a notice in writing is given to him in that behalf by the NIA / Architect / Authorised official.
- 3) Fails to complete the works or items of works within individuals / particular date of completion on or before the date (s) of completion and does not complete them within the period specified in a notice given in writing on that behalf by the NIA/Architect.
- 4) Shall offer or give or agree to give to any person in NIA service or to any other person on his behalf any gift or considerations of any kind as an inducement or reward for doing or for bearing to do or for having done or fore borne to do any act in relations to obtaining or execution of this or any other contract for NIA.
- 5) Shall obtain a contract with NIA as a result of running tendering or other non bonafide methods of competitive tendering or.
- 6) Shall obtain / enter into a contract with NIA in connection with which commission has been paid or agreed to be paid by him or to his knowledge unless the particulars of any such commission and the terms of payments thereof have previously been disclosed in writing to the competent Authority / NIA. Being an individual or if a firm any partner thereof shall at any time being adjudged insolvent or have a receiving order or order for administration of liquidations or composition (other than a voluntary liquidations for the purpose of amalgamation or construction) under an insolvent act for the time being in force or make any conveyance in assignment of his effective or composition or arrangement for the

benefit of his creditors or purpose so to, or if any applications be made under any Insolvency Act for the time being in force for the sequestration's of his estate or if a trust deed be executed by him for the benefit of his creditor or.

- 7) Being a company shall pass a resolution or the court shall make an order for the liquidation of its affairs or a receiver or manager on behalf of the debenture holders shall be appointed or circumstances shall arise which entitle the court or debenture holders to appoint a receiver or manager or.
- 8) Shall suffer an execution being levied on his goods and allows it to be continued for a period of 35 days.
- 9) Assigns, transfer, sublets (engagement of labours on a piece work basis or of labour With materials not to be incorporated in the work shall not be deemed to be subletting) or attempts to assign transfer or subject the entire works or any portion of the work without prior approval of the competent Authority. The competent Authority may without prejudice to any other right to remedy which shall have occurred or shall occur thereafter to the NIA by written notice cancel the contract as whole or only such items of work in default from the contract.
- 10) NIA shall on such cancellation have power to:
  - i. Take possession of the site and any materials, constructional plant / building etc., implements, stores etc
  - ii. Carry out the incomplete work by any means at the risk and cost of the contractor.
- 11) On cancellation of the contract in full or in part the site / authorized official shall determine what amount if any, is recoverable from the contractor for completion of the works or part of the works or in case of the works or part of the works is not to be completed the loss or damage suffered by NIA In determining the amount credit shall be given to the contractor for the value of contractor's materials taken over and incorporated in the work and use of tackle and machinery belonging to the contractor.
- 12) Any excess expenditure incurred or to be incurred by NIA in completing the works or part of the works or the excess loss or damages suffered or may be suffered by NIA as aforesaid after allowing such credit shall be recovered from any money are not sufficient the contractor shall be called in writing to pay the same within 30 days. If the contractor shall fail to pay the required sum within the aforesaid period of 30 days the NIA / Architect / authorised official shall have the right to sell any or all of the Contractor's unused materials, construction plant, implements, temporary buildings etc., and apply the proceeds of the sale thereof towards the satisfaction of any sums due from the Contractor under the contract and if thereafter there by any balance outstanding from the Contractor it shall be recovered in accordance with the provisions of the contract.
- 13) Any sums in excess of the amounts due to the NIA and unsold materials, construction plant etc., shall be returned to the contractor, provided always that if the cost or anticipated cost of completion by NIA of the work or part of the work is less than the amount which the contractor would have been paid and the completed the works or part of the works such benefit shall not accrue to the Contractor.

#### **D. TENDERS, RATES ETC.**

1. The work to be carried out under the contract shall except as otherwise provided in these conditions include all labour, materials, tools, plants, equipments and transport which may be required in preparation of and for and in the full and entire execution and completion of the works. The descriptions given in the schedule of quantities shall unless otherwise stated be held to included waste on materials, carriage and cartage, carrying in, return of empties, hoisting, setting, fitting and fixing in position and all other labours necessary in and for the full and entire execution and completion as aforesaid in accordance with good practice and recognized principles.
2. The attached bill of quantities is our best estimate of the job.
3. All the quantities therein are approximate, payments will be made on the actual measurements / certified by the Architect / NIA authorised official & project Architect.
4. NIA will have the right to omit, alter, add or cancel any of the items of work shown in the schedule without assigning any reason whatsoever and no claim for compensation will be entertained for the same, NIA is further at liberty to carry out any items of work departmentally or through any other contractor and no compensation will be paid to the main contractor on that account.

5. Work contained in the Schedule of Quantities comprises the erection of a reinforced concrete structure, with masonry walls, windows / doors, plastering / filling etc. water tanks, plumbing / sanitary work, interior works, electrical work and exterior work within the premises such as roads, paving etc.
6. Before submitting the Tender, the contractor shall visit and examine the site situated at **7E GIRIRAJ CHS, ALTAMOUNT ROAD, MUMBAI** satisfy himself /herself as to the nature of the existing roads or other means of communications, the character of the soil and of the excavations, the correct dimensions of the work facilities for procuring various construction and other materials and shall obtain generally his own information on all matters and conditions affecting the execution of the works. No extra charge made in consequence of any misunderstanding or incorrect information on any of these points or on the grounds of insufficient description will be allowed. The Contractor shall be deemed to have satisfied himself before tendering as to the correctness and sufficiency of his tender for the works and of the rates and prices quoted in the schedule of quantities which rates and prices shall except as otherwise provided cover all his obligations under the contract and all matters and things necessary for the proper completion and maintenance of the works.
7. It must be clearly understood that the whole of the conditions and specifications are intended to be strictly enforced and **that no extra work will be allowed unless they are clearly outside the spirit and meaning of the conditions and have been ordered in writing by NIA / Architect (authorised official)**
8. Before filling the Tender the Contractor will check all drawing and schedule of quantities and will get an immediate clarification from Architect / NIA as required on items not clearly understood. Any claim for any loss or compensation will not be entertained on this account.
9. The rates quoted by the Contractor shall be for finished work measured in site and should include supply of all materials labour, tools tackles, marking out and clearing of the site and liaison charges, with licensed plumbers for preparing plans, line out permission from Municipal Corporation, Statutory bodies etc. unless specifically mentioned otherwise. **The rates shall be exclusive of all taxes such as GST & other Tax if any**
10. The rates quoted by the Contractors should also include for providing all scaffolding, hoists, tackle and other plant, shuttering profiles and apparatus generally required for the proper execution of the work. The contractors shall provided without extra charges all labour and apparatus required by NIA for testing and measuring the works and for weighing measuring, providing or testing the efficiency of any portion of the works and shall also at his own cost provide all planking gang ways, etc. necessary for affording access to every part of the works.
11. The rates quoted by the Contractor should cover for necessary transport of materials from place of availability to the site of works.
12. The Contractor is expected to quote rate for each item after careful analysis of cost involved for the performance of the completed item considering all specifications and conditions of contract. This will avoid loss of profit or gain in case of curtailment or change of specification for any item. **In case it is noticed that the rates quoted by the tenderer for any item are Abnormally Low Rate(ALR). Analysis for such rates will have to be furnished by the tenderer on demand, to satisfy NIA about the reasonableness of the rates. NIA may demand additional security deposit for such ALR items in form of Bank Guarantee for difference of amount i.e. estimated rate minus quoted rates. Such additional SD shall be released on successful completion of project and certificate is issued thereof.**

#### **E. EXTRA ITEMS**

1. The NIA (authorised official) shall have the power to make any alterations in, omission from, addition to or substitutions for the schedule of rates the original specifications, drawings, designs and instructions that may appear to him to be necessary or advisable during the progress of the work and the Contractor shall be bound to carry out the such altered / extra / new items of work in accordance with any instructions which may be given to him in writing signed by the NIA, and such alterations, omissions, additions or substitutions shall not invalidate the contract and any altered additional or substituted work which the contractor on the same conditions in all respects on which he agreed to do the main work. The time for completion of work may be extended for the part of the particular job at the discretion of the NIA, for only such alternations, additions or substitutions of the work, as he may consider as just and reasonable. **The rates for such additional, altered or substituted work under this clause shall be worked out in accordance with the following provisions. :-**

- a. If the rates for the additional, altered or substituted work are specified in the contract for the work, the contractor is bound to carry out the additional, altered or substituted work at the same rates as are specified in the contract.
  - b. If the rates for the additional, altered or substituted work are not specifically provided in the contract for the work, the rates will be derived from the rates for similar class of work as are specified in the contract for the work. The opinion of the Architect / NIA, as to whether or not the rates can be reasonably so derived from the items in this contract, will be final and binding on the contractor.
  - c. If the rates for the altered, additional or substituted work cannot be determined in the manner specified in sub clause (a) & (b) above, then the contractor shall, within 7 days of the date of receipt of order to carry out the work, inform the NIA / Architect (authorised official) of the rate which it is his intention to charge for such class of work, supported by analysis of the rate or rates claimed, based on standard market rate analysis hand book published by NBO, and the NIA / Architect shall determine the rates on the basis of the prevailing market rates of materials, transport and labour plus 15% for overheads and contractor profit and pay the contractor accordingly. The opinion of NIA / Architect (authorised official) as to current market rates of materials and labour involved will be final.
2. Architect / NIA (authorised official) shall issue instructions to the contractor in regard to what is to be done concerning on object reported by the contractor under the proceeding sub clause and such instruction may be required to contractor to permit the examinations, excavations, or removal by a third party. Architect / NIA (authorised official) may issue instructions to the contractor in regard to be removal and disposal of the same at the expenses of NIA If in the opinion of the Architect / NIA, the above activity has involved the contractor indirect loss of time the NIA / Architect may allow extension of time for the completion of work equal in period to assessed loss of time on this account. The contractor shall not be eligible to claim any financial compensation due to any delay caused in this account.
3. NIA shall have the right to direct the contractor to purchase and use materials from any source for the proper execution of work.
4. Except if and to the extent otherwise provided by the contract, the provision of the General conditions of contract and special conditions shall prevail over those of any other documents forming part of the contract. Several documents forming the contract are to be taken as mutually, explanatory. Should there be any discrepancy inconsistency error or omission in the contract or any of them the matter may be referred to Architect / NIA who shall give his decisions and issue to the contractor instructions directing in what manner the work is to be carried out. The decision of the Architect / NIA (authorized official) shall be final and conclusive and the contractor shall carry out work in accordance with this decision.
5. Works shown upon the drawing but not mentioned in the specifications or described in the specifications without being shown on the drawings shall nevertheless be held to be included in the same manner as if they had been specifically shown upon the drawings and described in the specifications.
6. NIA reserves the right to accept or reject any or all the tenders without assigning any reasons. In other words, NIA do not bind themselves to accept the lowest of any tender.
7. Tender submitted by tenderer shall remain valid for acceptance for a period of 120 days from the date of opening of the tender. The tenderer shall not be entitled during the said period of 120 days, without the consent in writing of NIA to revoke, or cancel his tender. In case of revoking or cancelling his tender, varying any terms in regard whereof without the consent of NIA in writing the tenderer shall forfeit earnest money paid by him along with the tender.
8. In case of discrepancies between schedule of quantities, the specifications and or the drawings thereof, the following order of preference shall be observed.
  - i. Descriptions in Schedule of Quantities.
  - ii. Particular specification and special conditions, If any.
  - iii. Drawings:

In any case the most stringent of the above three shall apply. The decision of the NIA / Architect in this regard is final.

In case of varying or conflicting provisions made in any one document forming part of the Contract NIA shall be the deciding authority with regard to the intentions of the documents.

9. Any error in descriptions, quantities or rates in schedule of quantities or any omissions there from shall not vitiate the contract or release the contractor from the execution of the whole or any part of the work comprised therein according to drawings and specifications or from any of his obligations under the contract.

#### **F. PAYMENT TERMS**

1. Two Bills including the Final Bill (subject to retention and other deductions) will be made.
2. Income tax / cess / taxes / other / statutory levies if any shall be deducted from every running bills and final bill payment as applicable from time to time as per Government of India / State Government.
3. All running bills (if any) as well as final bills submitted in approved proforma shall be submitted to the Architect by the contractor in quadruplicate for certification. All the bill copies shall be accompanied by measurement sheets and quantity calculation in support of the quantities contained in the bill with soft & hardcopies.
4. All the works in progress will be jointly measured by the representative of NIA and the contractor progressively. Such measurements will be recorded in the measurement book by the NIA / Architect or his authorities representative and signed in token of acceptance by the contractor or his authorized representative.
5. All items having a financial value shall be entered in the measurement books, level book etc. prescribed by NIA that complete record is obtained of all work performed under the contract.
6. For the purpose of taking joint measurements the contractor's representative shall be bound to be present whenever required by the Architect. If, however, he is absent for any reason whatsoever the measurements will be taken by the NIA / Architect or his representative and these will be deemed to be correct and binding on the contractor.
7. The contractor shall without extra charges provide assistance with every appliance, labour and other things necessary for measurement of work

#### **G. METHODS OF MEASUREMENTS:**

1. Except where any general or detailed description of work in quantities expressly shows to the contrary schedule of quantities shall be deemed to have been prepared and measurements shall be taken in accordance with the procedure laid forth in specifications notwithstanding any provisions in the relevant standard method of measurement or any general or local custom. In the case of items which are not covered by the specifications, measurements shall be taken in accordance with the relevant and latest standard method of measurement issued by the Bureau of Indian Standards. (All Measurements will be noted as per actual without any rounding off)

#### **H. DEFECT LIABILITY PERIOD (DLP)**

1. The contractor shall **guarantee the installation/work for a period of 12 months from the date of issue of completion certificate**. Any damage or defect that may arise or lie undiscovered at the time of issue of completion certificate, connected in any way with the equipment or materials supplied by him or in the workmanship shall be rectified or replaced by the contractor at his own expense as deemed necessary by NIA or in default, NIA may cause the same to be made good by other workmen and deduct expenses (of which the certificate of NIA shall be final) from any sums that may be the or at any time thereafter, become due to the contractor or from his security deposit, or the proceeds of sale thereof, or of a sufficient portion thereof.
2. At the end of the defects liability period the contractor shall submit a written application for release of retention money. NIA shall release the money only after ensuring that all the defects pointed out by NIA/Architect till completion of DLP have been rectified by the contractor satisfactorily.
3. Any amount found due from the contractor to NIA from time to time will be recovered currently from the running bills. Similarly if, at any time, should there evidence of any lien or claim for which NIA might have

become liable and which is chargeable to the contractor, NIA shall have the right to retain out of any payment then due or thereafter to become due an amount sufficient to completely indemnify NIA against such lien or claim and if such lien or claim remain unsettled after all payments are made, the contractor shall refund or pay to the owner all money that the latter may be compelled to pay in is charging such lien or claim including all costs reasonable expenses.

4. The contractor will be fully responsible for rectifying any defects brought to his notice by NIA / project Architect in writing **within seven days of receipt of the intimation**. In case the contractor fails to attend to defects as stipulated therein, NIA reserves the right to complete the rectification through another agency of its choice and recover the cost of such repairs from the contractors dues against running bills/ final bill / retention money for this or any other job.

#### **I. SECURITY DEPOSIT**

1. On acceptance of the tender, **the successful tenderer shall, within the time stipulated in the letter of intent, deposit with the Employer by Demand Draft, a security deposit of 1% (one percent) of the value of the contract,** before he is allowed to execute the contract and commence work.
2. Failure to deposit this additional amount, within the stipulated time which shall include any extension granted by the Employer at its discretion, will make the earnest money deposited by the tenderer liable to forfeiture and the acceptance of his tender shall be considered as withdrawn.

#### **J. LIABILITY FOR DAMAGE, DEFECTS AND RECTIFICATION THEREOF**

1. If the Contractor or his workmen or employee shall injure or destroy any part of the building in which they may be working or any building road, fence etc., contiguous to the premises on which the work or any part of it is being executed or if any damage shall happen to the work while in progress, the contractor shall upon receipt of a notice in writing in the behalf make the same good at his own expenses. If it shall appear to the NIA / Architect or his representative at any time during the construction or re-construction or prior to expiration of defects liability period that any work has been executed with unsound, imperfect or unskilled workmanship or that any materials or articles provided by the contractor for execution of the work are unsound or of a quality inferior to that contract for, or otherwise not in accordance with the contract or that any defect, shrinkage or other faults have appeared in the work arising out of defective or improper materials or workmanship, the contractor shall upon receipt of a notice in writing in that behalf from the Architect / NIA forthwith rectify or remove or reconstruct the work so specified in whole or in part as the case may require or as the case may be and / or remove the materials or articles so specified and provide other proper and suitable material or article.
2. At his own expenses, notwithstanding that the same may have been inadvertently passed, certified and paid for and in the event of his failing to do so within the period to specified by the NIA / Architect may rectify or remove and re execute the work and / or remove and replace with other, materials or articles complained of, as the case may be by either means at the risk and expense of the Contractor.
3. In case of repairs and maintenance works, splashes and droppings from white washing, painting etc., shall be removed and surface cleared simultaneously with completing of these items of work in individual rooms, quarters or premises etc., where the work is done without waiting for completion of all other items of work in the contract. In case the contractor fails to comply with the requirement of this condition the Architect / NIA shall have the right to get the work done by other means at the cost of the Contractor. Before taking such action, however, the NIA / Architect (authorized official) shall give three days' notice in writing to the contractor.

#### **K. OVER PAYMENTS AND UNDER PAYMENTS:**

1. Wherever any claim for the payment of a sum of money to NIA out of or under this contract against the Contractor the same may be deducted by NIA from retention money / Security deposit or any sum then due or which at any time thereafter may become due to the contractor under this contract and failing that under any other contract with NIA or from any other sums due to the contractor from NIA which may be available with NIA he shall pay within ten days the claim in cash / Demand Draft on

- demand.
2. NIA reserves the right to carry out post payment audit and technical examinations of the Running / final bill including all supporting vouchers, abstracts etc. NIA further reserves the right to enforce recovery of any overpayments when detected, notwithstanding the fact that the amount of the final bill may be included by one of the parties as items of disputes before an arbitrator appointed under condition of this contract and notwithstanding the fact that the amount of the final bill figures in the arbitration award.
  3. If as a result of such audit and / or technical examinations any overpayments is discovered in respect of any work done by the contractor or alleged to have been done by him under the contract it shall be recovered by NIA from the Contractor by any of all methods or made of recovery as prescribed above or if any under payment is discovered, the amount shall be duly paid to the contractor by NIA.

#### **L. COMPLETION PERIOD AND COMPENSATION CLAUSE**

1. The Contractor shall commence work within 7 days from the date of receipt of letter of intent / email from NIA confirming that the purchase order is being awarded to him. The formal purchase order will be typed and mailed in due course after the letter of intent. Completion period for the entire work contained in the tender and such of the extra items, if any, which form an integral part of the contract, contained in the tender **is 120 days from the date of commencement of work at site as specified in above.** The time limit specified herein will be strictly adhered to and will form the essence of the Contract. 1% of total contract value per week up of two maximum of 5%, there after the owner may get the work done at contractor's risk and cost.
2. The successful contractor will be required to **submit PERT / CPM analysis** of the entire work within 10 days of issuing the LOI showing completion **period as 120 days.** Progress of the work shall be checked with the PERT / CPM analysis at various stages of completion. NIA shall have the right to terminate the contract ex-party if progress of the work is found to be unsatisfactory and there are no efforts from the contractor's side to make up for the delays if any.

#### **M. COMPLETION CERTIFICATE**

1. The work shall be considered "Virtually Complete" only after the Contractor submits to Architect / NIA the following documents obtained by him through his licensed plumber / Licensed electricians.
  - a. As soon as the work is completed the contractor shall give notice of such completion to Architect / NIA and within thirty day of receipt of such notice, Architect /NIA shall inspect the work and shall furnish the contractor with a certificate of completion indicating.
    - i. The date of completion.
    - ii. Defects to be rectified by the Contractor and /or.
    - iii. Items for which payment shall be made at reduced rates.
2. When the separate periods of completion have been specified for items or groups of items, Architect / NIA shall issue separate completion certificate for such item or group of items. No certificate of completion shall be issued, nor shall the work considered to be complete till the contractor shall have removed from the Employers premises on which the work has been executed all scaffolding, sheds, temporary structures and surplus materials except such as are required for rectification of defects, removal all huts and sanitary arrangements required for his workmen on the site in connection with the execution of work as such have been erected by the Contractor or the workmen and clear all dirt from all parts of the building (s) in upon or about which the work has been executed thereof and clean floor, all gutters and drains, ease doors and shutters, oil locks and fastenings, labeled keys clearly and handed them over to the NIA or his representative and made the whole premises fit for immediate occupations or use to the satisfaction of the NIA.
3. If the contractor shall fail to comply with of the requirements of these conditions as aforesaid on or before the date of completion of the works, NIA may at the expense of contractor arrange to remove scaffoldings, surplus materials and rubbish etc., as he thinks fit and the contractor shall have no claims in respect of any such scaffolding or surplus materials except for any sum actually realized by the sale there of less the cost of fulfilling to requirements any other amount that may be due from the contractor. If the expense of fulfilling such requirements is more than the amount realized on such disposal as aforesaid the contractor shall forthwith on demand pay such excess.



4. The whole of the work including all extra and additional items if any and when ordered are to be completed in the time stated in the contract and the contractor will be required if necessary to work overtime to stick to NIA requirements to complete all the works by the stipulated date. No extra claim for extension of completion period will be allowed on account of this factor.
5. The completion period of the entire work as stated above shall be deemed to be the essence of the contract. In case of delay in completing the work beyond the specified completion date the contractor will be required to pay a penalty at the rate of 0.5% of the total contract value per week subject to maximum of 5% of the actual cost of the project, there after the owner may get the work done at contractor's risk. The penalty will be recovered either from the contractor's bills or from the Security Deposit / Retention Money.
6. In case of delay of over 5 weeks in completion of the work beyond a stipulated completion date, NIA reserves the right to terminate the contract and get all the jobs completed through another agency of its choice. Any extra expenditure that NIA will have to incur for completion of the balance jobs through another agency on account of higher rates quoted by the agency will be recovered from the contractor's Security Deposit, Retention Money and pending bills.

#### **N. Extension of completion period**

If the work is delayed by

1. Force Majeure
2. Serious loss or damage by fire or
3. Civil commotions, local combinations of workmen, strikes or lockout affecting any of the trades employed on the work, or
4. Delay on the part of other contractors or tradesman engaged by NIA in executing work not forming part of contract.
5. Non – availability of stores, which are the responsibility of NIA to supply.
6. Non-availability or breakdown of tools and plant to be supplied or supplied by NIA.
7. Request for extension of time to be eligible for considerations, shall be made by the contractor in writing within fourteen days of the happening of the event causing delay. The contractor may also if practicable, indicate in such a request the period for which extension is desired.
8. In any such case NIA may give a fair and reasonable extension of time for completion of work. Such extension shall be communicated to the Contractor by NIA in writing within one month of, the date of receipt of such request by NIA.

**SPECIAL INSTRUCTIONS RELATED TO CARRYING OUT THE STRUCTURAL WORKS IN THE TENDER**

1	The above Demolition / Dismantling / Shifting / Resifting & Refixing works are to be carried out up to the 8th, 7th Floor & 6th Floor level. The serviceable and unserviceable materials shall be stacked separately and properly in the designated place and to be secured in safe custody till the disposal/refixing of the same. Sufficient manpower shall be provided for movement of furniture, fixture and elements to be shifted, reused and refixed, during execution. The debris is to be carted outside the premises and disposed off at the Municipal Corporation designated place up to any lead, lift and level.
2	The rates quoted for all the items of the BOQ shall include the following specifications:
a	All the works are to be carried out at all heights and locations
b	Providing and fixing scaffolding wherever required on the inside as well as exterior side, up to any height (entire height) of the building structure as approved and directed by the Architect & removing it thereafter.
c	The scaffolding system shall be stiffened with bracings, runners, connection with the building fascias etc wherever required & including providing vertical supports which shall be sound and strong, tied together with horizontal steel / metal support pieces over which scaffolding planks shall be fixed properly & secured at required locations including the essential safety features for the workmen etc complete as per directions and approval of Architect or Engineer-in-charge. Note: - The scaffolding shall not be removed without prior approval of Architect or Engineer-in-Charge.
d	Providing & fixing temporary support arrangements such as Steel Props (Up to any number whenever and wherever as directed by the Architect) to support the structure provisionally during repairs and structural works etc and maintaining the props in position till required & as directed by the consultant including other safety elements such as bracings, steel angles, working platforms, plates etc, which shall be provided & considered in the quoted rates for the areas in the vicinity in adequate numbers as directed. All the civil & structural Repair works indicated hereinunder shall include all leads & lifts & working up to any heights, depths & levels.
e	Providing temporary plywood, 6mm thk covering to the existing glass panes of windows / openings / doors / windows; before starting of the repair works to avoid damage including the removal of the same after completion of the works, cleaning and making good to the local damages, if any etc complete. The rate shall be also inclusive of temporary wooden partitions in 6mm thk plywood including ply door shutters at the desired locations wherever instructed including sealing joints with POP / masking tapes etc complete.
f	Providing & fixing safety net around the work so that loose plaster/ concrete does not cause damage to the property or any human being, if necessary and removing the same after completion of work.
g	Providing and covering entire external surface with Hessian cloth curtains so that not cause any damage to the existing structures near the building and even take care of dust control and carefully removing the same after completion of work.
h	Providing all type of PEE to the work-force such as safety shoes, safety helmets, reflective safety jacket, full body safety harness, goggles, gloves, etc. complete for all types of work-force engaged on site for execution of the work.
i	All the above mentioned points including the requisite elements & items as mentioned shall be considered included within the quoted rates of the line items of the BOQ and nothing extra would be paid on this account.
j	Loose Concrete shall be removed part by part by propping the remaining area and strengthening part by part either by polymar or micro concrete as directed by the Architect / Engineer.
k	The reinforcement shall be cleaned & coated with proactive coat of Polymer slurry. (polymer + Cement slurry)
l	Steel Bar to be added wherever necessary only after direction of Architect/ Consultant. The bar to be welded or as directed by the Architect.

m	The portion from which concrete has been removed shall be filled up by polymer modified mortar, while applying Bond coat or Micro Concrete as per the direction of the Architect/Consultant.
n	After the concrete is reinstated/brought to original line-level, then below slabs ISMB 100 shall be fixed with 150 x 150 mm x 6mm thick MS Plate with 4 nos 12mm thick anchor faster bolt and welding, as per the detailed drawings attached.
o	Lastly all RCC shall be plastered including curing.
p	The Contractor first mark the damaged area and start removing the damaged and loose concrete only after clearance given by the Architect/ Consultant.
q	The Contractor should ensure that whenever M/S Barve Consultants representative comes for inspection of work and direction if any should brought our and NIA Engineers before carrying out the work.
r	The Contractor should present at site for pre-bid meeting whereby the scope of work will be shown at site, Society's timing for carrying out work, society's restriction of disposal of debris and place where they can initially load and unload the material and their consultant's visit during the work.
	Make:
	1) Micro Concrete : BASF / Fosroc / Sika / Sunanda or equivalent approved by Architect/Engineer
	2) Polymer Modified Mortar : BASF / Fosroc / Sika / Sunanda or equivalent approved by Architect/Engineer
	3) Rust Remover : BASF / Fosroc / Sika / Sunanda / Pidilite or equivalent approved by Architect/Engineer
	4) Anti-Corrosive Primer : BASF / Fosroc / Sika / Sunanda / Pidilite or equivalent approved by Architect/Engineer
	5) Waterproofing Compound : BASF / Fosroc / Sika / Sunanda / Pidilite or equivalent approved by Architect/Engineer
	6) 53 Grade OPC Cement : ACC / Ultratech / Lafarge or equivalent approved by Architect/Engineer
	7) Waterproofing Make : Pidilite Industries Ltd. / BASF India Ltd. / Sunanda Speciality Coatings / Sika / Fosroc / Asian or equivalent approved by Architect/Engineer
	8) CPVC Pipes : Astral / Prince / Supreme
	9) PVC Pipes : Astral / Prince / Supreme

## **SITE FACILITIES**

### **A. SETTING OUT OF WORK**

1. The NIA / Project Architect shall supply dimensioned drawings levels and other information necessary to enable the Contractor to set out the works. The Contractor shall provide all setting out apparatus required and set out the works and be responsible for the accuracy of the same. He shall amend at his own cost and to the satisfaction of the NIA / Project Architect any error found at any stage which may arise through inaccurate setting out unless such error(s) is / are based on incorrect data furnished in writing by NIA / Project Architect in which case the cost shall be on the account of NIA. The Contractor shall protect and preserve all bench marks liability period unless the NIA / Architect directs their removal.

### **B. SITE DRAINAGE:**

1. All water which may accumulate on the site during the progress of works or in trenches and excavations from other than the expected risks shall be removed from the site to the satisfaction of the NIA / Architect at the Contractor's expenses.

### **C. NUISANCE**

1. The contractor shall not at any time do cause or permit any nuisance on the site or do anything which shall cause unnecessary disturbance or inconvenience to others at or near the site of work.
2. The contractor shall all times give access to the staff of statutory bodies as well as other agencies associated with the project and shall provide them all facilities like scaffolding, water, lighting etc. at site for discharging their duties.
3. No residential accommodation provided to the workmen/labor at the site. NIA reserve the right for the same
4. The Contractor shall provide at his cost all temporary lighting arrangement required for the works and to enable contractors and sub-contractors to complete the works in the specified time including that for the workmen of any sub – contractors or special tradesmen.
5. NIA may provide **Electricity power on non-chargeable basis** for the works mentioned in the tender at one point. The necessary all electrification, wiring, lighting arrangement (including separate meter installation) shall be made available by the contractor and for which contractor shall not be paid any charges for the same. Misuse of electricity power shall be charged as 0.1% of contract value.

### **D. WATCHING AND LIGHTING:**

1. The contractor shall provide and maintain at his own expense all lights, guards, fencing and watching when and wherever necessary or required by the NIA / Project Architect for the protection of the works or for the safety and convenience of those employed on the works or the public.

### **E. EQUIPMENT & STAFF ASSISTANCE FROM THE CONTRACTOR**

1. Theodolite, levels, plumb bobs, prismatic compass, chain, steel and metallic tapes and all other surveying instruments found necessary on the works shall be provided by the Contractor for the due performance of their contract as instructed by NIA. The NIA / Architect will use any or all measurement instruments or tools belonging to the Contractor as and when he chooses for checking the complete works as well as the work in progress.
2. All scaffolding and ladders that may be necessary for taking measurement at site will be provided by the Contractor.
3. The Contractor shall provide the following minimum equipment and machinery in good working condition at site during the entire period of construction/renovation as and when required.
4. The Contractor will be allowed to work for 8 (Eight) hours a day and 7 (Seven) days a week. However, no concreting shall be done during night or in the absence of the NIA / Architect. For working beyond normal working hours the Contractor shall obtain prior permission from the NIA / Architect.

## EXECUTION

### A. Admission to Site :

1. The Contractor shall not be permitted to enter on (other than for inspection purposes) or take possession of site until instructed to do so by the Architect / NIA in writing. The portions of the site to be occupied by the Contractor shall be defined and / or marked on the site plan failing which these shall be indicated by the NIA / Architect at site and the operations beyond the areas. In respect of any land permitted by NIA for the use of the Contractor for the purpose of or in connection with the contract. The same shall be subject to the following and such other terms and conditions as may be imposed by NIA.
2. The such use or occupations shall not confer any right of tenancy of the land to the contractor.
3. **THE CONTRACTOR HAS TO CARRY OUT THE WORKS AS PER THE TIMINGS OF THE SOCIETY NORMS.**
4. **The Society does not permit execution of work on Sundays/Public Holidays.**
5. **The Materials can be stored or kept temporarily at the designated parking of the flat 7E**
6. The Contractor shall have no right to put up any constructions of his own of any nature or type on NIA land except temporary constructions for storage of equipment for the work under the contract or as a resting place for labourers employed by him for the work provided that he obtained the requisite previous permission in writing from NIA or from the Architect in accordance with NIA procedure which permission they would be entitled to refuse in their absolute discretion. Such construction will be erected at the contractor's own cost.
7. If any electricity is used in any of such constructions the Contractor shall himself pay for the same. The Contractor shall at his own cost demolish all such constructions and remove the debris thereof, as also all his materials and equipment's and clean and level the site thereof before handing over the completed work to NIA.
8. The Contractor shall provide if necessary or if required on the site all temporary access thereof and shall alter adapt and maintain the same as required from time to time and shall take up and clear them away as and when no longer required and as and when ordered by the NIA / Architect and made good all damages done to the site. The Contractor shall note that the final bill will not be certified for the payment till the action as above is completed by the Contractor to the entire satisfaction of the NIA / Architect (Authorised official)
9. All the work shall be carried out as per detailed drawings and instructions of the Architect / NIA (Authorised official)
10. All drawings, tracings, photo prints and writings (except letter) shall be the sole property of Architect / NIA and must be returned to them on completion of the works.
11. The drawings maintained on the site are to be carefully mounted on boards of appropriate size and covered with a coat of approved varnish. They are to be protected for ravages of termites, ants, silver fish and other insects.
12. The completion of the work may entail working in the monsoon also.
13. The contractor must maintain a minimum labour force as may be required for the job and plan and execute the construction and erection according to the prescribed schedule. No extra rate will be considered for such work in monsoon.
14. During the execution of the work, Contractor must check his work with the drawings. The Contractor shall be responsible for all the errors in this connection and shall have to rectify all defects and / or error at his own cost, failing which NIA reserves the right to get the same rectified at the risk and cost of the Contractor.

### B. MATERIAL TO BE PROVIDED BY THE CONTRACTOR.

1. The Contractor shall at his own expense and without delay supply to the NIA / Project Architect, samples of materials proposed to be used in the work. The NIA / Project Architect shall within 15 days of supply of samples or within such period as he may require intimate to the Contractor in writing and inform the Contractor whether samples are approved by him or not. If the samples are not approved, the Contractor shall forthwith arrange to supply to the NIA / Project Architect for his approval fresh samples complying with the specification laid down in the contract. A set of all approved samples shall be maintained at site under lock & key by the Architect / NIA.

2. Architect / NIA shall have full power to require removal of any or all the materials brought to the site by the Contractor which are not in accordance with the contract specifications or do not confirm in character or quality to sample approved by him. In case of default on the part of the Contractor in removing rejected materials, the Architect / NIA shall be at liberty to have them removed by other means. The Architect / NIA shall have full power to procure other proper materials and in the event of the Contractor refusing to comply, he may cause the same to be supplied by other resources. All costs which may attend upon / incurred upon such removal and / or substitution shall be borne by the Contractor.
3. The Contractor shall indemnify NIA or any employee of NIA against any action, claim or proceeding relating to infringement or use of any patent or design or any alleged patent design rights and shall pay any royalties or other charges which may be payable in respect of any articles or materials or part thereof included in the contract. In the event of any claim being made or action being brought against NIA or any agent, servant or employees of NIA in respect of any such matters as aforesaid the Contractor shall immediately be notified thereof.
4. NIA / Project Architect shall be entitled to have **tests carried out as specified in the contract for any materials supplied by the Contractor**, other than those for which as stated above, satisfactory proof has already been furnished, at the cost of the Contractor and the Contractor shall provide at his expense all facilities which the NIA / Project Architect require for the purpose. IF no tests are specified in the contract and such tests are required for the purpose and the charges for these tests shall be borne by the Contractor only. The cost of materials consumed in the test shall be borne by the Contractor in all cases except when otherwise provided.
5. Representative of NIA connected with the contract, shall be entitled at any time to inspect and examine any materials intended to be used in or on the work, either on the site or at factory or workshop or at other place (s) manufactured or at any places where these are laying or from which these are being obtained and the Contractor shall give such facilities as may be required for such inspection and examination.
6. Trees designated by the NIA / Project Architect shall be protected from damages during the course of the works and earth level within 1 metre of each such tree shall not be damaged, when necessary such trees shall be protected by providing temporary fencing.

#### C. LABOUR

1. The Contractor shall employ labour in sufficient number either directly or through sub – contractors when such subletting is permitted to maintain the required rate of progress and of quality to ensure workmanship of the degree specified in the contract and to the satisfaction of the NIA / Architect. The Contractor shall not employ in connection with the works any person who has not completed his Eighteenth year of age.
2. In case of any class of work for which there is no such specification supplied by NIA as is mentioned in the tender documents, such work shall be carried out in accordance with Indian Standard Specifications and if the Indian Standard Specifications do not cover the same the work should be carried out as per standard Engineering practice subject to the approval of the Architect /NIA.
3. The contractor shall on the written request of NIA / Architect immediately dismiss from the works any person employed by him therein who may in the opinion of NIA be incompetent or misconduct himself and such person shall not again be employed on the works without the written permission of NIA/Architect(authorized official)
4. The Contractor or his agent shall be in **attendance at the site (s)** during all working hours and shall supervise / superintend the executions of works with such additional assistance in each trade as the NIA / Architect may consider necessary. Order given to the Contractor agent shall be considered to have the same force as if they have been given to the Contractor himself.
5. Architect / NIA shall communicate or confirm his instructions to the Contractor in respect of the executions of work in a **“work site order book”** maintained in the office authorised representative shall confirm receipt of such instructions by signing the relevant entries in the book.
6. Any instructions issued by the Architect / NIA orally, shall be of no immediate effect but shall be confirmed in writing by the Contractor to the site NIA / Architect within seven days and if not dissented from in writing by the Architect / NIA to the Contractor within 7 days from receipt contractor's confirmation shall take effect as from the expiration of the lettersaid 7 days of giving such oral instructions shall himself confirm the same in writing, then the Contractor shall not be obliged to confirm as aforesaid and the said instruction shall take effect as from the date of NIA / Architect confirmation and provided that if neither the Contractor nor the Architect / NIA shall confirm such oral instructions in the manner and at the time aforesaid but the

Contractor shall nevertheless comply with the same then the Architect / NIA may confirm the same in writing at any time prior to the issue of the Final certificate and the said instructions shall thereupon be deemed to have taken effect on the date on which it was issued.

7. The Contractor shall provide and do everything necessary for the proper execution of the works according to the true intent and meaning of the drawings and specifications taken together, whether the same may or may not be particularly shown on the drawings, or described in the Schedule of Quantities, provided that the same can be reasonably inferred therein from. Figured dimensions and all dimensions and particulars to be taken from the actual work.
8. The whole of the work must be proceed with such sections and at such times as directed by NIA
9. Architect / NIA (authorised official) may from time to time issue further drawings or written instructions which are hereafter collectively referred to as 'Architect's Instructions' in regard to:
  - i. The variation or modification of the design, quality or quantity of works or the addition or omission or substitution of any work.
  - ii. Any discrepancy in the drawings or between the schedule of quantities and / or drawings and / or specifications.
  - iii. The removal from the site of any materials brought thereon by the contractor and the substitution of any material therefor.
  - iv. The removal or re-execution or both of any works executed by the Contractor.
  - v. The dismissal from the works of any persons employed thereupon.
  - vi. The opening up for inspection of any work covered up.
  - vii. The amending and making good of any defects of works improperly carried out.
10. The contractor shall forthwith comply with and execute any work comprised in such Architect's Instructions. Any instructions given verbally shall be deemed as instructions for the proper execution of the works as long as they do not involve any extra charges.
11. If the Contractor after receipt of written notice from the Architect / NIA requiring compliance within seven days fails to comply with such drawings or Architect instructions or both as the NIA / Architect may issue, NIA may employ and pay other persons to execute any such drawings or Architect instructions and all cost incurred in connection therewith as certified by the Architect shall be borne by the Contractor or may be deducted from any amount due or that may become due to the contractor under the contract or may be recovered as a debt.

#### **D. INSPECTIONS AND APPROVALS:**

1. All works embracing more than one process shall be subject to examinations and approval at each stage thereof and the Contractor shall give due notice to the NIA / Project Architect shall be entitled to appraise the quality and extended thereof.
2. No work shall be covered up or put out of view and without approval of Architect NIA or his authorized representative and the Contractor shall afford full opportunity for examination and measurement of any work which is about to be covered up or put out of view and for examination or foundations before permanent work is placed thereon. The Contractor shall give due notice to the NIA / Project Architect or his authorised representative wherever any such work or foundation is ready for examination and the NIA / Project Architect or his representative shall without unreasonable delay unless he considers it unnecessary and advises the Contractor accordingly attend for the purpose of examination and measuring such work or of examining such foundation he shall, if required by the NIA / Project Architect uncover such work at the Contractor's expenses.
3. Duties and powers of NIA / Project Architect and his authorised representative and other officers of NIA. The duties of the representative of the NIA / Project Architect are to watch and supervise the progress of works and to test and examine any materials to be used or workmanship employed in connection with the

works. They shall have no authority to order any work involving any extra payment by NIA or to make any variations in the works except when authorised by the NIA. The NIA / Architect may from time to time in writing delegate to his representative any of the powers and authorities vested in him and shall furnish to the contractor a copy of all such written delegation of powers and authorities. Any written instructions of written approval given by the representative of NIA / Architect to the Contractor within terms of such delegations shall bind the Contractor and NIA as though it had been given by the NIA / Architect.

4. Failure of the representative of Architect to disapprove any work or materials shall not prejudice the power of the NIA / Architect thereafter to disapprove such work or material and to order pulling down removal or breaking up thereof.
5. If the Contractor shall be dissatisfied with any decisions of the representative of the Architect / NIA he shall be entitled to refer the matter to the Architect / NIA who shall thereupon confirm, reverse or vary such decisions.
6. The whole of the materials (except where otherwise described), stores and equipment required for the faithful performance of the contract must be provided through normal trade channel, and must be the best of their kind available at the time and the Contractor must be responsible for the proper and efficient carrying out of the work. The work must be done in best and most workmanlike manner. Samples of all materials to be used must be submitted to the Architect / NIA on the site for approval prior to procurement. The Contractor shall furnish to the Architect / NIA for approval when requested or if required by the specifications, adequate samples of all materials and finished to be used in the work. Such samples shall be submitted before the work is commenced and in ample time to permit tests and examinations thereof. All materials finished and applied in actual work shall be fully equal to the approved samples.
7. During inclement weather the Contractor shall suspend concreting and plastering for such time as the Architect / NIA may direct and shall protect from injury all works in the course of erection.
8. Should the work be suspended by reason of rain, strike, lockouts or other cause the Contractor shall take all precautions necessary for the protection of the work and at his own expense shall make good any damages arising from any of these causes.
9. The Contractor shall keep accurate records of weather, temperature, visitors and any other occurrences affecting the progress or quality of the works.
10. All shavings, cuttings and other rubbish as it accumulates from time to time during the progress of the works and at completion including that of sub – Contractor and specific tradesman to be cleared and carted away and all materials condemned by the Architect / NIA shall be removed from site as and when required during the entire duration of the work at no extra cost.
11. The Contractor shall protect all projecting eills and mouldings and all concrete steps from injury during the progress of the work by rough timber casings securely fixed.
12. The Contractor shall provide all necessary templates, moulds for circular or shaped work, carpenters or joiners work or any other trade.
13. The Contractor shall protect joinery and make good all damages to the same from any cause whatsoever



during the performance of the contract and leave perfect to the satisfaction of the Architect / NIA at the time of completion. Before giving up possession, the contractor must see that all doors sashes etc. work easily and shall make all necessary adjustments.

14. The Contractor shall provide suitable stone with flat tops and build the same in concrete for temporary bench marks. All the pegs for setting out the work and fixing the necessary levels required for the execution thereof shall if desired by the Architect / NIA likewise be built in masonry at such places and in such manner as NIA may determine.
15. Particular care must be taken to see that the floors are not overloaded by stacks of materials during construction. It is important that no load comes on the reinforced concrete floors until they are at least 3 weeks old and at no time must the load placed upon them exceed the load for which they are designed
16. The Contractor has to provide all necessary holes, slits and depression etc. in form work and concrete to place pipelines or ancillary services in any form as shown in the drawings or as directed by NIA
17. The Contractor shall cover up and protect from injury from any cause all new work also for supplying all temporary doors, protection to windows and any other requisite protection for the whole of the works executed whether by himself or specified tradesmen or sub contractors and any damage caused must be made good by the contractors at his own expenses.
18. The Contractor shall provided temporary teakwood barricading upto 4' 0" height from the floor level to all lift walls and / or shafts opening on all floors to safeguard against any accidental fall and maintain them till such time as permanent enclosures are installed. No extra payment will be allowed on the contract sum for complying with this clause.

#### **E. STATUTORY**

1. The contractor shall conform to the provisions of any regulations and by – laws of any water or lighting companies with whose system the structures are proposed to be connected and shall before making any variations from the drawings that may be necessitated by so conforming give to the Architect / NIA on site written notice specifying the variations proposed to be made and the reason for making to and apply for instructions thereon. In case the contractor shall in due course receive instructions, he shall proceed with the work, conforming to the provision regulations or by-laws to the supply companies and shall provide for and pay all fees and charges.
2. The contractor will be fully responsible for complying with all relevant provisions of the Contractor Labour Act and shall pay rates of Wages and observe hours of work/ conditions of employment according to the rules in force from time to time.
3. The contractor shall comply with provisions of payment as per the following acts : Payment of wages Act, 1936, Workmen's Compensation Act, 1923 Industrial Dispute Act, 1947 Minimum Wages Act, 1948 Employees State Insurance Act, 1948 Maternity Benefit Act, 1961, Mines Act, 1952 or
4. Any amendments / modifications thereof or any other law relating thereto and rules made there under from time to time. NIA / Architect shall on a report having being made by an inspecting office as defined in the

contract labour regulations have the power to deduct from the money due to the Contractor any sum required or estimated to be required for making good the loss suffered by a worker (s) by reasons of non – fulfillment of conditions of contract for the benefit of workers non – payment of wages or of deductions made from his or their wages which are not justified by the terms of contract or non observance of the said contractor’s labour Regulation.

5. The contractor shall pay to labour employed by him, and in the case of his giving any part of the work on sub – contract he shall ensure and be responsible to see that the sub – contractor pays to labour employed by such contractor, wages not less than wage or remuneration as provided in the contract labour (Regulations and Abolition Act) and in the Rules, Regulations and orders.
6. The Contractor shall indemnify the NIA against any payments to be made under and for observance of the Regulations aforesaid without prejudice to his rights to claim indemnity from his sub - contractor.

#### **F. SAFETY CODE:**

1. The Contractor shall at his own expenses arrange for the Safety provisions as amended to these conditions or as required by the NIA / Architect in respect of all labours directly or indirectly employed for performance of the works and shall provide all facilities in connections therewith. In case the contractor fails to make arrangements and provide necessary facilities as aforesaid, the NIA / Architect shall be entitled to do so and recover the cost thereof from the Contractor. Safety precaution to be taken in all respects (till completion of works) including for all concern human being. The contractor shall be responsible for any damage or loss of part / limb or death human being.
2. From the commencement to the completion of the works, the contractor shall take full responsibility for the care thereof and of all the temporary works (defined as meaning all temporary works of every kind required in or for the execution, completion or maintenance of the works). In case damage, loss or injury shall happen to the works or to any part thereof or to temporary works or to any cause whatsoever (save except the Expected Risks as defined in) repair at his (Contractor’s) own cost and make good the same so that at the time of completion, the works shall be in good order and condition and in conformity in every respect with the requirements of the contract and NIA instructions. In the event of any such damage, loss or injury happening from any of the Expected Risks the contractor shall if any to the extent required by NIA repair and make good the same as aforesaid at the cost of NIA.

#### **G. INSURANCES**

1. The Insurance for the following will be covered and paid for by the contractor, and contractor shall indemnify the NIA and hold the NIA harmless in respect of all and any expenses arising from any such injury and / or damages in respect of:
  - a. Workmen’s Compensation and Risk of Accidents to contractor’s own employees.
  - b. Contractors all risk Insurance to cover the total cost of project with third party coverage.
2. The contractor has to insured building/site under construction/renovation till completion and it should be place to be employer in the name of the NIA. Contractor shall submit the copy of policy details within 15 days of receipt of LOI/Work order.

3. If the contractor and / or his sub contractor fails to effect and keep in force the Insurance referred to above or else where in the contract or any other insurance which he may be required to effect and keep in force, NIA reserves the right to keep in force and such insurances and pay such premium or premia as may be necessary for the purpose and from time to time deduct the amount so paid by NIA as aforesaid from any moneys due or which becomes due to the contractor or recover the same as a debt from the contractor.
4. The aforesaid insurance policy / policies shall not be cancelled till the Architect / NIA has agreed to their cancellation.
5. The Contractor shall prove to the Architect / NIA from time to time that he has taken out all insurance policies referred to above and has paid the necessary premium for keeping the policies alive till the expiry of the defects liability period.
6. The contractor shall ensure that similar insurance policies are taken out by his sub- contractor (if any) and shall be responsible for any claims of losses to NIA resulting from their failure to obtain adequate insurance protections in connection thereof. The contractor shall produce or cause to be produced by his sub – contractor (if – any) as the case may be, the relevant policy or policies and premium receipts as and when required by the Architect /NIA.

#### **H. NOTICE TO LOCALBODIES.**

1. The contractor shall comply with and give all notices required under any Government authority, instrument, rule or order made under any act of parliament, state laws or any regulations or by-laws of any local authority relating to the works. He shall before making any variations from the contract drawings necessitated by such compliance give to the NIA / Architect a written notice giving reasons for the proposed variations and obtain the Architect instruction therein.

#### **I. ARBITRATION**

1. All disputes or differences of any kind whatsoever which shall at any time arise the parties hereto touching them or concerning the work or execution or maintenance thereof this Contract or the construction operation or effect thereof or to the rights or liabilities of the parties or arising out of or in relation thereto whether during or after determination, foreclosure or breach of this contract (other than those in respect of which the decision of any person is by the contract expressed to be final and binding) shall after written notice by either party to the contract or the other of them and to the Appointing Authority who shall be appointed for this purpose by the Employer, be referred for adjudication to a sole arbitrator to be appointed as here in after provided.
2. For the purpose of appointing the sole Arbitrator referred to above, the Appointing Authority will send within thirty days of receipt by him of the written notice aforesaid to the Contractor, a panel of the three names of persons who shall be presently unconnected with the organization for which the work is executed.
3. The Contractor shall on receipt by him of the names as aforesaid, select any one of the persons named to be appointed as a sole Arbitrator and communicate his name to the Appointing Authority within thirty days of receipt by his the names. The Appointing Authority shall thereupon without any delay appoint the said person as the sole Arbitrator, if the Contractor fails to communicate such selections as provided above within the period specified, the appointing authority shall made the selection and appoint the selected person as the sole Arbitrator.
4. If the appointing Authority fails to send the Contractor the panel of three names as aforesaid within the period specified, the Contractor shall send the Appointing Authority a panel of three names of persons who shall be unconnected with either party. The Appointing Authority shall on receipt by him of the names

- as aforesaid select any one of the persons named and appoint him as a sole Arbitrator. If the Appointing Authority fails to select the person and appoint him as the sole Arbitrator within 30 days of receipt by him of the panel and inform the Contractor accordingly, the Contractor shall be entitled to appoint one of the person from the panel as a sole arbitrator and communicate his name to the Appointing Authority.
5. If the Arbitrator so appointed is unable or unwilling to act or resign his appointment or vacate his office due to any reason whatsoever another sole arbitrator shall be appointed as aforesaid.
  6. The work under the Contract shall, however continue during the Arbitration proceeding and no payment due or payable to the Contractor shall be withheld notice on account of such proceedings.
  7. The Arbitrator shall be deemed to have entered on the reference on the date he issues notice to both the parties fixing the date of the first hearing.
  8. The Arbitrator may from time to time, with the consent of the parties, enlarge the time for making and publishing the Award.
  9. The Arbitrator shall give a separate award in respect of each dispute in accordance with the terms of the Contract and give a reasonable award.
  10. It is also a term of the Contract that if Contractor (s) do/does not make any demand for arbitration in respect from the Clients / Architects that the bill after due verification is passed for payment of a lesser amount, or otherwise, the arbitration shall be deemed to have been forfeited and Client / Architects shall be relieved and discharged of their liability under this agreement in respect of such claim(s). Further, it is agreed that for the purpose of this clause such notice is deemed to have been received by the Contractor(s) within 2 days of posting of the letter by Clients / Architects or when delivered by hand immediately after receipt thereof by the Contractor(s), whichever is earlier. Further, a letter signed by the officials of Clients / Architects that the letter was so posted to the Contractor(s) shall be conclusive.
  11. The Fees, if any of the Arbitrator shall, if required be paid before the award, be paid half and half by each of the parties. The costs of the reference and of the award including the fees, if any of the Arbitrator who may direct to and by whom and in what manner, such costs or any part thereof shall be paid and may fix or settle the amount of costs to be so paid.
  12. The award of the Arbitrator shall be final and binding on both the parties.
  13. Subject to a fore said, the provisions of the Arbitration and Conciliation Act 1996, or any statutory modification of re- enactment there of and the rules made there under, and for the time being in force, shall apply to the Arbitration proceeding under this Clause.

### **SPECIAL CONDITIONS OF CONTRACT**

1. It shall be distinctly understood that notwithstanding the reviews and suggestion if any, by the NIA or Project Architect the sole and ultimate responsibility for the stability and performance of the form work and staging and all other temporary works shall be that of the Contractor.
2. The partners or Directors of the Contractor shall meet the officers of NIA or its consultants at the site of works or at their respective offices whenever requested to do so.
3. The Project Architect shall supply to the contractor reasonably complete engineering drawings. All **the drawings required for the complete execution** of the work shall be submitted by the Architect within 7 days of issue of work order. **Bar bending schedules and shop drawings** required for proper execution of work shall be prepared by the Contractor and submitted well in advance within 14 days of issue of work order to NIA and its Project Architect to permit scrutiny, corrections resubmissions and final approval without causing any delay in the construction/renovation work.
4. The Contractor shall confirm to the provisions of the Government Act relating to the work, and to the regulations and bye-laws of the local authorities. The contractor shall give all notices required by the said act, and obtain all required permission and license and pay all fees payable to such authorities in connection with constructing and maintaining temporary electric and water supply at site for the said project. All aspects of temporary works including their stability shall be the sole and ultimate responsibility of the Contractor.
5. NIA reserves the right to use the premises and any portion of site for execution of any work not included in this contract which NIA may desire to get executed by other agencies. The Contractor shall allow all reasonable facilities for the execution of such work but shall not be required to provide any plant or material for such work except by special arrangement with NIA in such a manner as not to impede the progress of the works included in this contract and the Contractor shall not be responsible for any damage or delay which may happen or be occasioned by such work.
  - i. In addition to previous stipulations, the Contractor shall be represented at site at all times during the tenure of the contract by responsible and qualified engineers approved by NIA Such engineer shall form the Contractor's Project Management & Site Supervisory Team. They shall be in constant attendance upon all activities of the work. Contractors staff shall comprise of at least the following to be permanently on site for the entire duration of the project.
    1. Engineer (Diploma holder with at least 7years' civil and interior works experience) – 1person.
    2. Jr. Engineer(Min. 5years' experience having Diploma Holder civil and interior works experience) – 1persons.
  - ii. Cost of recovery against materials, utilities or services supplied or arranged for by NIA shall be made by deducting the respective amount from the running as well as final bills.
6. Although Schedule of Probable Quantities & Rates has been divided into various sub – section, the rates quoted for a particular item of work in one sub – section shall be made applicable to similar item of work in any other sub – section if that item is not listed in the Schedule of that other sub –section.

7. This project is subjected to inspection by various audit / vigilance agencies of Government of India / NIA if any inspection of works is carried out by such agencies contractor shall extend his full co-operation to these agencies in examining records, works etc. on inspection by such agencies, any and in their inspection report, if it is pointed out that Contractor has not carried out work according to guideline laid down in this tender documents and also if any recoveries in some items is pointed out therein, same shall be recovered from contractor's R. A. Bills / Final Bill. The items under dispute shall not be paid in full till inspection agency gives their no objection report.
8. This work being prestigious NIA, quality of materials & workmanship are expected from the contractor of very high standard.
9. The successful tenderer is bound to carry out any item of work up to any deviation in quantities, for the completion of the job.
10. The Electrical works is to be executed through licensee electrical contractor only.
11. Material testing report can be asked for by NIA. The contractor must cooperate with the employer (NIA) to make available such reports from the manufacturer of the material used in the tender with no extra cost.
12. NIA shall be the sole deciding authority on the brand and make of the materials to be used.

#### **SCHEDULE – F**

1	Earnest Money Deposit	:	<b>10000/-</b>
2	Initial Security Deposit	:	1% of the total tendered amount (for successful bidder)
3	Defects Liability Period (DLP)	:	12 months from the date of issue of <u>virtual completion</u> certificate and handing over the completed work to owners
4	Period of commencement	:	7 days from the date of letter of intent / work order
5	Duration of completion of work	:	<b>120 days</b>
6	Liquidated damages at the rate	:	0.5% of total contract value per week up of to maximum of 5% of the contract value, there after the owner may get the work done at contractor's risk and cost i.e. beyond delay of 5 weeks
7	Retention money	:	a) 10% retention money to be kept from every running bill - to be released after completion of DLP  b) Security deposit to be released on expiry of the defects liability period after rectification in executed works.
8	Terms of rate	:	The rates shall be at site of work and Should be excluding of GST
9	Period of validity of tender	:	120 days from opening of tender
10	Period for honouring interim bill	:	The interim bills if raised shall be paid within 15 days of receipt from the architect)
11	Validity of rates after award of work	:	The rates shall be firm for period of 4 Months from the date of award of work or till final completion of work whichever is later. <b>“NO ESCALATION IN PRICES WILL BE ALLOWED”</b>

12 Minimum value of work of Interim bill : **50% of the work. Max 2 bills to be raised including Final Bill**

13. Upon it becoming reasonably apparent that the work is delayed, the contractor shall forthwith give written notice of the cause of the delay to the client and the Architect. Then the client and the Architect shall as soon as they are able to estimate the length of the delay beyond the date or time aforesaid, make in writing a fair and reasonable extension of time for completion of the work, provided always that the contractor shall use constantly his best endeavour to prevent delay and shall do all that may reasonably be required to the satisfaction of the client and the Architect to proceed with work.
14. **Damage for non-completion:** If the contractor fails to complete the works by the date specified in the conditions or within any extended time fixed, the contractor shall pay to NIA a sum calculated at the rate stated in the special conditions as agreed liquidated damages for the period during which the said work shall so remain or have remained incomplete. The client may deduct such damages from any money that is otherwise payable to the contractor, under this contract.
15. **Extra Items :** All authorised extra items where rates cannot be derived from tender the contractor shall submit rates, supported by rate analysis worked on the 'actual cost basis' plus 15% towards establishment charges, contractor's overhead and profit & GST etc
16. **Deviation in Quantities:** There is no variation limit in tender quantity, for any variation in plus or minus, contractor is supposed to execute the same at quoted rates.
17. **Photographs :** The rate quoted shall include the cost of supplying colour photographs of 8" x 10" size including soft copy to employer after completion of work from various angle one set each to Employer and the architect separately in respect of each floor/dept as directed.



## **GENERAL SPECIFICATION**

This specification are for the work to be executed items to be supplied and materials to be used in the works as shown and detailed on the drawings and described here in all under the supervision and to the satisfaction of the Architect /Employer.

The workmanship is to be the best available and of a high standard. Use must be made of specialist tradesmen in all aspects of the works, and allowance must be made in the rates for doing so.

The materials and items to be provided by the contractor shall be the best of their respective kinds, approved by the architect in accordance with any samples which may be submitted for approval and generally in accordance with the specifications. Where materials or products are specified in this specification and or / bill of quantities by the name of the manufacture or the brand trade name or catalogue reference the contractor will be required to obtained the approval of the architect / employer before using a material or product other than the specified. The contractor shall produce all invoices, vouchers or receipted accounts for any materials if called upon to do so by the Architect.

**Sample of all material** are to be submitted to the architect for his approval **within 10 days of issue of work order** before the contractor orders or delivers in bulk to the site. Also, the contractor will be required to submit specimen finishers of colors, fabrics etc, for the approval of the architect before proceeding with the works. Should it be necessary to prepare shop drawings, then four copies of such drawings shall be submitted for the approval of the architect who will retain ONE copies all at the contractors expenses.

### **TIMBER :**

Timber generally is to be best of its kind, well and properly seasoned, of mature growth, free from worm holes large loose or dead nodes or other defects and sawn die square and will not suffer warping, splitting or other defects through improper handling.

The hardwood is to be C.P. teak weighing not less than 45 lbs cubic foot with a moisture content tax.

Timber is to be cut to the required sizes and length as soon as practicable after the works are begun and stored under cover so that the air will circulate freely around it. Journey is to be prepared, immediately after the placing of contract, framed up (but not bonded) and stored until required for fixing in position, when it is to be bonded and waged up. Any portions that warp or develop shakes or other defects are to be replaced before wedging up, the whole of the work is to be framed and finished in a proper and workman like manner in accordance with the detailed drawings and fitted with all necessary motaties straps, belts screws etc. running bonded joints are to be cross tongued with teak on gress and where over 1 – 1/28 thick double tongued. Joiner's work generally unless otherwise specified. Templates boxes and moulds shall be accurately set out and rigidly constructed so as to remain accurate during the time they are in use.

Grounds are to be clean shown, free large knots, splayed as required, plugged and fixed to walls etc. at 1'6" centers. Wood plugs are to be cut on the twist, patent wall plugs or plastic filling may be used in lieu of wood plugs with the approval of the Architect.

All unexposed surfaces of timber e.g. false ceilings, backings fillets backs of doors frames, cupboard framing, grounds etc. are to be treated with ONE coats of approved timber preservative like solignum, kirticite, term seal or cast oral or vacuum pressure impregnated with and approved water soluble timber preservative before fixing or bedding.

The quality of timber shall be checked and ensured by the Architect.

### **JOINTS**

All joints will be standard, mortised and tenon, dovetail, dowe, cross halved, metered tongued and grooved and rebated, nailed or glued but joints, will not be permitted except in exceptional cases, ailed but joints will not be accepted. All joins shall be smeared with white lead.

Whenever solid wood is specified it shall be as per I.S.I. and of good quality. The type of wood shall be got approved before collecting the same on site. Fabrication of wooden members shall be started only after approval. It shall be free from large, loose, dead or cluster knots, flows, shakes, warps, bends or any other defect. It shall be uniform in substance and of straight fibers as far as possible. It shall free from rats, decay, harmful fungi and other dejects of its usefulness for the purpose for which it is required. The colour of wood shall be uniform as far as possible. The scantlings planks etc. shall be seen in straight lines and planes in the direction of grain and of uniform thickness.

**FIRST CLASS TEAK WOOD:**

First class teak wood shall have no individual hard and sound knots, more than 6 sq.cm. in size and the aggregate area of such knots shall not more than 1% area of piece. The timber shall be closed grained.

**SECOND CLASS TEAK WOOD:**

No individual hard and knot's shall be more than 15 sq.cm. in size and aggregate area of such knot's shall not exceed 2% of the area of piece.

**GLASS:**

All glass shall be of the best quality, free from specks, bubbles, smokes, veins, air holes, blisters and other defects. The kind of glass to be used shall be as mentioned in the item or specification or in the special provisions or as shown in detailed drawings. Thickness of glass panel shall be uniform. All glass to be approved manufacture complying with IS:3548-196 or as per approved quality and sample.

The compound for glazing to metal is to be special non hardening compound manufacture for the purpose and of 9 brand and quality approved the interior Designer.

In cutting glass, proper allowance shall be made for expansion. Each square of glazing to be in one whole sheet and after cutting the edges to be properly filled. On completion, clean all glass inside and out, replace all cracked scratched or broken panes and leave in good condition to the satisfaction of the Architect.

Only etching is to be used on glass panels. No frosting shall be used.

**MELAMINE FACED PARTICAL BOARD:**

It should be three layered wood based particle board, such as Nova pan melamine faced pre-laminated on both sides. Particle board should be ISI 3087 FPTH (type II, 1965 ) marked on edges and should also confirm to German din standard Viz DIN 66761. It should impart good bending strength, modules of elasticity, internal bond strength and screw holding strength. Melamine faced surface should has resistant to crack at 100 and should pass cigarette burn test.

**POLISH:**

The wooden article to be polished shall be first prepared to smooth surface with 400 fit black water proof sand paper. All dents shall be filled with epoxy putty and to be finally finished with DUCO, N.C. clear lacquer to a silk smooth finish.

**PLYWOOD:**

Plywood for general purpose shall confirm I.S.I. 303-1975.

**FASTENINGS AND HARDWARE:**

- 1 THE fixtures and fastenings, that is, but hinges, teened strap hinges, sliding door stoppers, casement window fasteners, casement stays and ventilators catch shall be made of the metal as specified in the item or its specifications.
- 2 They shall be of iron, brass, aluminium, chromium plated iron, chromium plated brass copper oxidized iron copper oxidized brass or anodized aluminum as specified.
- 3 The fixtures shall be heavy type. The fixtures and fastenings shall be smooth finished and shall be such as will ensure ease of operation.
- 4 The samples of fixtures and fastenings shall be got approved as regards quality and shape before providing them in position.

- 5 Brass and anodized aluminium fixtures and fastenings shall be bright finished.
- 6 Screws, nails, bolts, will be of brass or other non corrosive metal. In hardware, they will match the finish of the hardware tem.
- 7 Nails, in a finished surface shall be neatly punched and the hole filled with wood filler matching the finish. Screws, in a finished surface will be round head, raised head or sunk beneath the surfaces and the hole plugged with a wood plug with matching color and grain of the wood surface, unless especially detailed.

#### **HARDWARE:**

Hinges, locks, latches, door tracks etc. shall be as specified by the manufacture specified. In any variation of this quality of the substitute shall be equal to or better than the original specified, and samples should be submitted to the Architect for prior approval.

#### **HARDWARE AND METALS:**

The hardware throughout shall be of approved manufacture and supply well made and equal in every respect to the samples to be deposited with the Architect. The contractor any be required to produce and provided samples from many different sources before the Architect is able to make a decision and he should allow in his rates for so doing. Fittings generally shall have a satin chrome or anodized finish unless otherwise specified, and shall be suitable for their intended purposes.

Screws are to match the finish of the article to be fixed and to be rounded of flat headed or counter sunk as required. Cover up and protect at the brass and bronze surfaces with a thick grease or other suitable protective material, renew as necessary and subsequently clean off and clear away on completion.

Aluminium and stainless steel shall be of approved manufacture and suitable for its particular application. Generally the surfaces of aluminium shall have an anodized finish and both shall comply with the samples approved the Architect. All steel brass, bronze, aluminium and stainless steel articles shall be submitted to a seasonable test for strength; if so required by the Architect at the Contractor's expenses.

All brazing and welds are to be executed in a clean and smooth manner rubbed down and left in the flat test and tidiest way, particularly where exposed.

Chromium plated shall be in accordance with B.S. 1224 or as per approved specification and shall be on a base materials of copper or brass or as specified by Architect.

#### **ENAMEL PAINTS:**

Oil paints shall be of 1<sup>st</sup> quality and the specified colour and shade, and as approved. The easy mixed paints shall only be used. However, if ready mixed paint of specified shade or tint is not available while ready mixed paint with approved stainer will be allowed. In such a case, the contractor shall ensure that the shade of the paint so allowed shall be uniform.

All the paints shall meet with the following general requirements:

1. Paint shall not show excessive setting in a freshly opened full can and shall easily be re-disbursed with a paddle to a smooth homogeneous stage. The paint shall show no curdling, livering, caking or color separation and shall be free from lumps and skins
2. Paint as received shall brush easily, possess good leveling properties and show no running or slugging tendencies.
3. The paint shall not skin within 49 hours in a three quarters filled closed container.
4. The paint shall dry to a smooth uniform finish from the manufactures and generally according to their instructions and without any admixtures what so ever.

Ready mixed paint shall be used exactly as received from the manufactures and generally according to their instructions and without any admixtures what so ever.

#### **PLASTIC EMULSION PAINT:**

Pigmented priming coat (emulsion thinned with water) followed by three or more finishing coats of plastic emulsion paint. Pasted filler to be applied every coat exempting the final finishing coat and sanded.

Company name :ASIAN PAINTS  
Shade No. ROYAL ATMOS White – for walls  
Shade No. ROYAL ATMOS White – for ceilings  
Shade No. Plastic Emulsion White – for Utility area like kitchen, toilet .

**LAMINATES:**

All the laminate to be used shall be of 1.0 / 1.5 mm. thickness in approved the color and shade as proved and specified by the Architect. It shall be as given below.

Company name :Greenlam

Shade No. 5337 Malay Teak (1.00mm) OR

Shade No. 777 Sumatra Teak (1.00mm)

Edge binding 22/0.8mm of Rehau to match the laminate shades. Adhesive -Marine fevicol and Rehau Aquence Bondmaster. All the Grooves provided in between laminate as per drawings to be filled with Polish and exposed all edges with TW bedding Patti with melamine polish.

**veneers:**

The best quality natural wood veneers of the specified wood and of the specified thickness shall be used. It shall be in matching group and of uniform shade and as per the selection and approval. The contractor shall have to obtained the approval of the prior to pressing of veneers. The contractor shall have to use the brand of veneers as approved by the Architect.

**RUBBER:**

Natural latex rubber (Geo foam) of specified density and the thickness shall be used for all the cushions and padding for upholstered furniture. Loose cushions of all furniture should have solid foam walling to keep up proper shape.

**UPHOLSTERY :**

This will be of first class standard workmanship with webbing no- sag springs, padding and filling as specified on drawing. Covering fabrics will be shown tufted and corded as shown on the drawing.

**CUSHION VENTS:**

Brass or aluminum “cushion vents” should be installed at the back or underside of seat cushions (especially) those covered in leather evenly plastic or very tightly woven fabric) to allow air to escape and to prevent torn seams.

### **LIST OF INDIAN STANDARDS REFERED TO**

1. IS.No.1200–latest measurement of building and civil engineering work.
2. IS. No. 297 – 1973. Recommendation for maximum permissible moisture content of Timber used for different purposes in different climatic zones.
3. S. No. 1141 – 1973 code of practice for seasoning of timber.
4. I.s.No.6534–1971 guiding principles for grading and inspection of timber.
5. IS. No. 1200 (part XXI) 1973 : Method of measurement of building and civil engineering works. Part XXI wood work and joinery
6. IS. 3845 – 1966. Code of practice for joints used in wooden furniture.
7. IS. 4000 – 1967. Wooden flush doors. Type to method of test for.
8. IS. 4970 – 1973. Key for identification of commercial timbers.
9. IS. No. 3364 (part II) – 1975, Methods of measurement and evaluation of defects in timber, part II converted timber
10. IS. No. 1703 – 1969. Methods of testing small clear specimens of timber.
11. IS. No. 6342 – 1971. Rosewood logs for production of sliced veneers.
12. S. No. 5248 – 1969. Teak logs for production of sliced veneers.
13. I.S.No.2202(part I) 1973. Specification for wooden flush door shutters (solid core type part plywood).
14. S. No. 2338 (part I) – 1967. Code of practice for finishing of wood and wood based materials part I operations and workmanship.
15. S. No. 7630 – 1975. Methods of sampling of plywood.
16. S. No. 303 – 1975. Specification for plywood for general purposes.
17. S. No. 3129 – 1965. Specification for article board for insulation purposes.
18. S. No. 3513 – 1966. (part III & part IV). High and medium density wood based laminates part III general purposes. Part IV sampling test.
19. S. No. 1659 – 1979 blockboards.
20. S. No. 7316 – 1974. Decorative plywood using plurality of veneers for decorative faces.

21. S. No. 3478 – 1966. High density wood particleboards.
22. I. S. No. 1734 (part I to XX). Plywood method of test for Part I : General; Part II: Plywood ; Part III : Battens
23. S. No. 1328 – 1970. Veneer decorative plywood.
24. S. No. 710 – Marineply.
25. S. No. 3087 – 1965. Wood particle boards (Medium density)
26. S. No. 848 – 1974. Specification for synthetic resin adhesives for plywood. (Phenolic & Aminoplastic)
27. I. S. No. 2046 – 1969. Specification for decorative laminate.
28. I. S. No. 8273 – 1976. Fibrous gypsum plasterboards.
29. I. S. No. 2095 – 1964. Gypsum plasterboards.
30. I. S. No. 2542 (part I) – 1978. Gypsum plaster concrete and products, methods of test for part I – plaster and concrete.
31. I. S. No. 8272 – 1976. Gypsum plaster for use in the manufacture of fibrous plasterboards.
32. I. S. No. 2441 – 1963. Fixing coiling coverings code of practice for.
33. I. S. No. 2835 – 1977. Specification for flat transparent sheet glass.
34. I. S. No. 2395 (part I) – 1966 & 2395 (part II) – 1967: Painting to concrete, masonry, plaster surfaces code of practice for part – I operation and workmanship part II – schedule.
35. I. S. No. 3548 – 1966. Glazing in building code of practice for.
36. I. S. No. 6278 – 1971. White washing and colour washing code of practice for.
37. I. S. No. 137 – 1965. Specification for ready mixed paint brushing, matt or egg – shall flat finishing, interior to Indian standards colours as required.
38. I. S. No. 133 – 1975. Specification for ready mixed paint brushing. Wooden coating, interior to Indian standard colours.
39. I. S. No. 129 – 1950. Specification for ready mixed paint brushing grey filler for enamel for use over primer.
40. I. S. No. 129 – 1950. Specification for ready mixed paint brushing, finishing, interior, oil gloss, for general purposes to Indian standard colours.
41. I. S. No. 120 – 1950. Specification for ready mixed paint brushing grey filler for enamel for use over primer.
42. I. S. No. 533 – 1973. Specification for gum spirit of turpentine (oil of turpentine).
43. I. S. No. 101 – 1964. Methods of test for ready mixed paints and enamel.
44. I. S. No. 75 – 1973. Specification for linseed oil, and refined.
45. I. S. No. 77 – 1976. Specification for linseed oil, oiled for paint.

46. I. S. No. 124 (part I) – 1976. Specification for ready mixed paint brushing, finishing, semi glosses, for general purposes.
  47. I. S. No. 5884 – Specification for woollen carpets.
  48. I. S. No. 104 – 1979. Specification for ready mixed paint brushing, finishing, zinc chrome primer.
  49. I. S. No. 5391 – 1969. Adjustable metal chairs for use of typist and operators in telephone exchanges.
  50. I. S. No. 8756 – 1978. Ball catches for use in wooden mirrors.
  51. I.S.No.3499–1976(partII)chairs for office purposes metal revolving and tilting.
  52. I.S.No.5416–1969.General purpose wooden chairs methods of test for.
  53. I.S.No.6185–1971.High chair specification and safety requirements for.
  54. I.S.No.4116–1976.Joints used in wooden furniture code of practice for.
  55. I. S. No. 3845 – 1966. Joints used in wooden furniture code of practice for.
  56. I. S. No. 7070 – 1973. Shelving racks wooden (adjustable and non adjustable type).
    - a. adjustable type).
  57. I. S. No. 4414 – 1977. Table tops (wooden)
  58. I. S. No. 5967 – 1969., Tables, wooden, methods of test for.
  59. I. S. No. 3564 – 1975. Door closers (hydraulically regulated).
  60. I. S. No. 799 – 1979. Drawer locks, cupboards and box locks.
  61. I. S. No. 7981 – (part i I) – 1975. Glossary of terms relating to builders hardware – part I locks.
  62. I. S. No. 204 – (part I & II) 1978. Tower bolts ferrous metals and
  63. Non-ferrous metals.
  64. IS 456-2000: for Plain and Reinforced Concrete
  65. IS 5437-1994 for figured, rolled and wired glass
  66. IS 3548-1988: for glazing in buildings
  67. IS 10439-1983: for patent glazing
  68. IS 2835-1987: For flat transparent glass sheets
- NB. The various items to be used in the interior decoration work shall be of ISI standards. Whenever the items / products do not have ISI mark / standard, shall be got tested for its quality etc. at the laboratory and necessary testing charges shall be borne by the contractor.

#### **SCHEDULE OF APPROVED MAKES**

**Note: The Contractor should obtain prior approval from Architects before placing order for any specific material / agency.**

LIST OF MAKE FOR CIVIL WORKS

S.no	Material		Brand/ Manufacturers OR EQUIVALENT
1	Cement	:	OPC 53 grade conforming to BIS-8112 and approval
2	Reinforcement Steel	:	TMT steel conforming to BIS-1786 and approval of source by Engineer
3	Ready Mix Concrete	:	ACC, BIRLA, Ahlcon or approved equivalent
3	Doors & Windows fixtures/ Fittings:	:	Kitch, Hettich
4	Door Hardware & Fixture	:	Kitch, Hettich
5	Aluminium Sections.	:	Hindalco, Jindal, Indal, Bhorka,
6	Clear Glass/ Clear Float Glass / Toughened Glass	:	Saint Gobain(SG), Modi, AIG
7	Laminates	:	Greenlam, Aica, Sunmica, Archid
8	Synthetic Enamel Paints	:	Berger (Luxol gold), Asian(Apcolite), ICI Dulux (Gloss),
9	Oil Bound Distemper	:	Asian (Tractor), Berger (Bison), Nerolac
10	Cement Paint	:	Snowcem Plus, Berger (Durocem Extra), Nerolac (Nerocem with titanium),
11	Plastic Emulsion Paint	:	Asian paints Royal Atmos
12	Back-up Rod.	:	Supreme Industries or equivalent
15	Metal Fire Check Doors	:	: Navair, Ozone, Godrej
16	Gypsum Board System	:	India Gypsum,
18	Admixtures for concrete.	:	Cico, Kryton ,Penetron
21	Flush Door Shutters.	:	Century, Archidply, Green Ply
22	WPC Board		Alstone or equivalent
23	Plywood / Block Board		GreenPly , Century , Archidply,
24	Teak ply		GreenPly , Archidply
26	High Pressure Laminate		Prodima, Fundermax , Trespa
27	Adhesive for Wood work		Fevicol , Vamicol
28	Glazed Tiles	:	RAK,
29	PVC Water Stops	:	Supreme, Astral, Prince
30	White Cement.	:	Birla White, J.K.
31	Powder Coating Material Pure Polyester.	:	Jotun , Berger, GoodlassNerolac
32	Pre-coated G.S Windows & Door frames		NCL or equivalent
33	Masking Tapes	:	Sun control , Wonder Polymer.
35	Dash Fasteners./Anchor bolts	:	Hilti, Fischer, Bosch.



38	E.P.D.M. Gaskets.	:	AnandReddiplex, Enviro Seals
39	Weather & Structural Silicon.	:	Dow Corning, Wacker, GE
40	PVC continous fillet for periphery packing of Glazings /Structural glazings.:	:	Roop, Anand, Forex Plastic.
41	Water proofing compound		Pedilite,Kryton, Penetron
43	Water proofing / Injection Grouting	:	Specilized agency as approved by engineer
44	6mm thick Reflective Glass	:	Glaverbel, Glavermas, Saint Gobain.
45	Multicolor Steel Roofing Sheet		Alviva Steels Ltd, Everest
46	Vitrified Tiles	:	RAK
48	Aluminium Cladding sheets	:	Alstrong ,Alstone,Alucobond
49	Stainless steel D-handles	:	Kitch, Ozone, Hettich
50	Stainless Steel Railing 304 &316(Welding less)	:	Q-Rail, Kitch ,Arch
63	Metal False ceiling	:	Grid Square , Armstrong , Hunter Douglas
64	Calcium Board & Tile(Ceiling /Partion/Panelling)	:	Hilux or equivalent
67	Compact Laminate sheet	:	Merino , Green Lam
68	AAC Block	:	J.K.Laxmi Cement Ltd , Kannav Builders Pvt ,Ecolite
69	Wall Putty	:	Laticrate , Birla white, J.K White
70	Chairs (ISI marked)		Spacewood , Godrej , Wipro, Zitten
71	Tilebase		Tileceil/Armstrong

**NOTE**

1. Wherever make have not been specified for certain terms as equivalent makes referred,the same shall be as per BIS and as per approved by Engineer-in-charge/Consultant.

**LIST OF MAKE FOR PLUMBING WORKS**

S.no	Material		Brand/ Manufacturers OR EQUIVALENT
1	Vitreous China Sanitary ware	:	Jaquar
2	Stainless Steel Sink	:	Jaquar , Commander, Nirali
3	Plastic seat cover of W.C	:	Jaquar
4	Geyser	:	Racold, Voltas, Bajaj
5	C.P. Fittings Mixer/Pillar taps Washers, C.P. brass accessories	:	Jaquar,
6	Centrifugally /Sand cast iron pipes & fittings	:	Neco, Hepco
7	G.I. Pipes	:	Jindal-Hissar, Tata, Prakash-Surya B.S.T., SAIL,
8	G.I. Fittings	:	Jindal-Hissar, Tata, Prakash-Surya B.S.T., SAIL,
9	Gunmetal Valves	:	Zoloto, Leader,
10	Brass stop & Bib Cock	:	Zoloto, Sant, L&K, Jaquar
11	Ball valve with floats	:	Zoloto, Leader, Sant, Jayco
12	Stoneware pipes & Gully Traps	:	IS Marked pipes
13	R.C.C. pipes	:	IS Marked pipes
14	D.I. Manhole Covers	:	RIF, NECO,

15	Water Tank	:	Sintex, Polycon, Uniplast
16	Mirror	:	Golden, Atul, Modi guard ,Gujrat Guardian
17	Hand drier	:	Kopal, Automat, Euronics
18	PVC flushing cistern	:	Parryware, Hindware,Jaqvar
19	Insulation of Hot water pipes	:	Vidoflex insulation, Superlon insulation or equivalent
20	PVC Rain Water Pipes.	:	Supreme, Prince, Finolex. Astral
21	Sluice valve / NRV	:	Kirloskar, Kilburn, Zoloto ,Castle,
22	Water supply pumps	:	KIRLOSKAR, WILO, GRUNDFOS
23	UPVC pipes & fittings	:	Finolex , Prince, Supreme, Astral
24	Chlorinator	:	ALFA, USA, Ion exchange, Sigma DH Combine Inc.
25	HDPE Solution tank	:	WATCON, ION EXCHANGE, Water Supply Specialist P (Ltd)
26	C.P Flush Valves	:	Jaquar, Seiko, Nelson
27	C.P Angle Valves, bib cock	:	, Jaquar, Seiko ,Nelson
28	Level controller	:	Femac or equivalent
29	Drainage Pumps	:	Grundfos, KSB, Kirloskar
31	R.O System	:	Thermax, Aqua Process, Ion-Exchange, Akar-Impex, Polycon Technologies, Fontoos
32	PE-AL-PE	:	Kitec, Jindal, NEXGEN
33	HDPE pipes and fittings	:	Oriplast, So-Soon, Finolex
34	Infrared Sensor operated Urinals	:	Jaquar, Euronics,U-tec
35	Grab Bars	:	Marino or equivalent
36	CPVC pipe	:	Prince, Supreme,Finolex, Astral
37	Solar Panel	:	Tata BP, BHEL, EMMVEE
38	Copper Pipe	:	Raj Co., Maxflo
39	Copper Fittings	:	Viega, IBP
40	Lab drainage	:	Viega or Equivalent as approved.
41	Lab Fittings	:	Vijay, Viega, or equivalent
42	CP Grating for Floor Trap	:	Chilly,Cardin, Cammry
43	UPVC Over Head Water Tank	:	EURO, SYNTEX, DIPLAST

#### LIST OF MAKES FOR ELECTRICAL WORKS

S.no	Material		Brand/ Manufacturers OR EQUIVALENT
1	KV VCB Panel Board	:	Siemens// Voltas/Crompton Greaves/L&T/
2	KV XLPE Cable	:	Incab/ Universal/ NICCO/ CCI
3	Transformer	:	Crompton Greaves/ GECAlstom/Voltamp Areva/ ABB
4	Bus Duct/rising mains (Sandwich)-	:	L&T/ Siemens/ ABB/Legrand

5	Diesel Engine	:	Cummins/Kirloskar/Cotton
6	Alternator	:	Stamford/ Kirloskar/ Leroy Somer &Control/ Crompton Greaves/ Cater pillar
7	Battery	:	Exide/Standard Furrukawa /Amar ,Raja
8	L.T. Cables	:	
		:	Skytone / KEI/ Poly Cab/ RR cable
9	PVC insulated Wires/Telephone wires & cables India Co-axial cables	:	Finolex / Havells / RRCable
10	Telephone Tag Blocks	:	Krone Type
11	Modular Range of Switches,sockets etc	:	Anchor- Roma /RR Switch / Havells –Crab tree.
12	Industrial Sockets & Plugs	:	Siemens//Legrand/Gewiss/ Havell"s
13	M.S. Conduit	:	BEC/ AKG/ M Kay/ NIC/ Siddarth/ Harsh
14	Light fixtures.	:	Philips/ Halomax / Trilux
15	Ceiling Fan/ Exhaust fan	:	Crompton Greaves/ Usha/ Bajaj.
16	Main LT Panel	:	Manufactured at the works of L&T, Siemens,Legrand , Schneider only.
17	MV Panels	:	Venus Controls,Neptune,Advance,ASG control & Switchboard Pvt. Ltd.Anand Power Ltd.,System & Power Control.Amptech.,Nitya Electrical Controls,Ambit Switchgear Pvt. Ltd,Adlec.
18	Air Circuit Breakers	:	L&T,Legrand,Siemens,ABB,Schneider
19	MCCB	:	L&T/ Legrand/ Siemens/ ABB/Schneider
20	MCB-DB"s, MCB, ELCB	:	L&T/ GE Power Controls/ Siemens/Legrand
	RCCB/ MCB-Isolator etc.	:	Schneider, Legrand
21	SDFU	:	L&T/ GE Power Controls/ Siemens/ Schneider
22	Power Contactors	:	L&T/ Legrand/ Siemens/ Schneider/ABB
23	LIFTS	:	OTIS/ Kone/ Scheindler/ Mitubshi/Johnson
24	EPABX	:	Siemens, Ericsson, Alcatel, Avaya
26	FDA Panel	:	Honeywell/Edwards/Minimax
28	BMS	:	ABB, L&T, Trane, Honeywell
29	UPS	:	Schneider Numeric, Emerson, Eton, Power ware
31	PA System	:	BOSCH,Harman,Bose
32	Access Control System	:	BOSCH, Honeywell, L&T

**Note:.. Any item not mentioned above shall be subject to approval by owners/consultant/Architect**

**Annexure-1-(Technical Bid)**THE NEW INDIA ASSURANCE CO. LTD

S.No.	ESSENTIAL/MANDATORY DOCUMENTS/CRITERIA			
1	Name and Address of the contractor			Address proof to be attached( <b>mandatory</b> )
2	PAN No & GST			Copy of each to be attached ( <b>mandatory</b> )
3	Tender Fee (Rs 590)			Scanned copy to be attached online and hard copy to be submitted to office ( <u>MSE are exempted</u> ) ( <b>MSE must submit scanned MSE certificate for claiming exemption</b> ) ( <b>mandatory</b> ) <b>Note-MSME certificate must be for Civil &amp; Repair Works</b>
4	EMD (Rs 10000)			Scanned copy to be attached online and hard copy to be submitted to office ( <u>MSE are exempted</u> ) ) ( <b>MSE must submit scanned MSE certificate for claiming exemption</b> ) ( <b>mandatory</b> ) <b>Note-MSME certificate must be for Civil &amp; Repair works</b>
5	Similar Works ( <b>Structural Repairs &amp; Restoration completed in last 7 years</b> )			Certificates/ <b>work completion certificates</b> to be attached for <b>similar work</b> (merely work orders will not be considered) ( <b>mandatory</b> ) [ Please note that the qualifying value should correspond to <u>one single work</u> /two single works/three single works ( <i>i.e. the bidder <b>should not</b> combine value of different small works to project as value of single work</i> )
	1 similar work amounting to 80% of estimated value i.e. Rs 35.2 lacs	2 similar works amounting to 50% of estimated value i.e. Rs 22.0 lacs	3 similar works amounting to 40% of estimated value i.e. Rs 17.6 lacs	
6	Self declaration regarding not disqualified /not blacklisted by any organization /bank in the past			To be attached ( <b>mandatory</b> )
7	Balance sheet / Profit & Loss Statement for the last 3 years. ( to be attached herewith )			To be attached ( <b>mandatory</b> )

Date:-

Place:-

**Annexure-2-**  
**(Security Deposit -Bank Guarantee Proforma)**

To,  
The Chief Manager  
Estate Dept.  
The New India Assurance Co. Ltd.  
Head Office

WHEREAS M/S ....., (hereinafter called “the Contractor”) has undertaken, in pursuance of Tender Reference No.....dated ..... to undertake works titled

“.....”

AND WHEREAS it has been stipulated by you in the said Tender that the Contractor shall furnish you with a Bank Guarantee by a recognized bank for the sum specified therein, as security for compliance with the contractor's performance obligations in accordance with the contract.

AND WHEREAS we have agreed to give the contractor a guarantee:

THEREFORE, WE hereby affirm that we are Guarantors and responsible to you, on behalf of the Contractor , up to a total of Rs.....(in words.....) and we undertake to pay you, upon your first written demand declaring the contractor to be in default under the Tender and without cavil or argument, any sum or sums within the limit of Rs...../- ( Amount of Guarantee) as aforesaid, without your needing to prove or to show grounds or reasons for your demand or the sum specified therein.

This guarantee is valid until the.....

Signature and Seal of Guarantors (Contractor’s Bank) Date:

Address:

**ANNEXURE-3 PRICE BID (Bill of Quantities)**

SR.NO.	PARTICULARS	QTY	UNIT	RATE	AMOUNT
<b>A</b>	<b>Structural Work</b>				
<b>1</b>	<p><b>I Section Beam &amp; Plates (As per Society's Consultants) After the concrete is reinstated/bought to original line-level, then below slabs ISMB 100 shall be fixed with 150 x 150 mm x 6mm thick MS Plate with 4 nos 12mm thick anchor faster bolt and welding, as per the detailed drawings attached.</b></p> <p>Providing, detailing, fabricating and fixing at desired location using hot rolled sections and MS Plates of grade Fe 250 as per specifications and approved fabrication drawings (which are to be prepared by Contractor and got approved from Architect/Engineer), transporting to site and erecting structural steel members for all heights &amp; at all levels including provision of necessary erection bolts, fixing bolts, nuts, washers, cleats, stiffeners, gussets, base plate, and all necessary fixtures and operations like preheating as per specifications, straightening, bending, cutting, drilling, grinding, machining if</p>	2,600.00	KG		

2	<p><b>Polymer Work for Beam Up To 30mm</b>  <b>Removing existing damaged Reinforced Cement Concrete by Chipping the surface and cleaning the rusted reinforcement and exposed surface by wire brush, mechanical device or any other established method at any height/depth and carrying away debris in gunny bags and the same is carting away</b>  <b>unserviceable material / debris to a place as shown at site by Architect and the same is to be carted away to a place approved by M.C.G.M.</b>  <b>a) REMOVAL OF RUST : Providing &amp; applying approved rust remover to clean reinforcement bars &amp; allowing it to react for specified time and cleaning the reinforcement of total rust by tapping or using mechanical wire brush around the reinforcement bars to give it a totally rust free finished steel surface using suitable tools and equipment</b>  <b>b) PASSIVATOR COAT ON REINFORCEMENT : Providing and applying one component , Polymer modified cementitious anti-corrosive primer formulated to provide dual protection of a polymeric barrier and an integral corrosion-inhibiting system to existing and additional steel provided before patching of damaged areas, using suitable tools and equipment and using BASF approved make chemicals of Master Emaco P130 / Fosroc Nitoprime Zincrich / Sika Rust off 100.</b>  <b>c) BOND COAT : Providing and applying bond coat on concrete surface by mixing high dispersion SBR latex like Master Emaco SBR2 of BASF or Nitobond SBR (Latex) of Fosroc with white cement in the ratio of 2:3. The mixing should be done to a lump free consistency for bond coat and screed mortar to be applied once the bond coat is tacky</b>  <b>d) POLYMER MODIFIED MORTAR (PMM) : Providing and applying up to 50mm thick Polymer modified mortar in ratio 1:5:15 (1 part by weight of Polymer : 5 parts by weight of cement : 15 parts by weight of washed Quartz sand) to the damaged concrete portion in two layers with required w/c ratio for desired consistency. The mortar shall be applied by hand and finished the same by floating coat complete as per manufacturer's specifications including curing, etc. at all height and locations complete.</b>  The approved brands are Master Emaco S348 of BASF / Renderoc HB-60 of Fosroc / Sikadur 41 of Sika. The rates also includes all types of scaffolding as applicable, safety net, green cloth etc.  Please Note: The Contractor should ensure that all stages (a to c) of Micro Concrete works to be passed by the Architect / Engineer-in-charge. The work has</p>	1320.00	SFT	
---	---	---------	-----	--

	<p>to be carried out at all heights / locations as per the instructions of Architect / Engineer-in-charge.</p> <p><b>The Contractor has to carryout this work by part by part strengthening ceiling polymer work by giving proper support by propping the slab as per the direction of the Architect</b></p>			
--	--	--	--	--



3	<p><b>Polymer Work for Ceiling Up To 30mm</b></p> <p>Concrete by Chipping the surface and cleaning the rusted reinforcement and exposed surface by wire brush, mechanical device or any other established method at any height/depth and carting away debris in gunny bags and the same is carting away unserviceable material / debris to a place as shown at site by Architect and the same is to be carted away to a place approved by M.C.G.M.</p> <p>Refer Same Specification as mentioned in item no. I-2</p> <p><b>The Contractor has to carryout this work by part by part strengthening ceiling polymer work by giving proper support by propping the slab as per the direction of the Architect</b></p>	3500	SFT		
4	<p><b>Polymer Work for Slab</b></p> <p>Concrete by Chipping the surface and cleaning the rusted reinforcement and exposed surface by wire brush, mechanical device or any other established method at any height/depth and carting away debris in gunny bags and the same is carting away unserviceable material / debris to a place as shown at site by Architect and the same is to be carted away to a place approved by M.C.G.M.</p> <p>Refer Same Specification as mentioned in item no. I-2</p> <p><b>The Contractor has to carryout this work by part by part strengthening ceiling polymer work by giving proper support by propping the slab as per the direction of the Architect.</b></p>	1000.00	SFT		
5	<p><b>Micro Concrete Work</b></p> <p>Providing encasement to columns / beams / pardi etc., with free flow high strength non shrink micro concrete M - 35 using single cement micro concrete shrinkage components added with 100% by weight saturated dry stone dust. The water cement ratio should be maintained as per manufacturer's specifications to achieve dense solid mass. The Micro concrete shall be poured properly in slurry tight prefixed holding boards formwork, fixed properly in line, level and in the required size/shape and well oiled etc. The air bubbles, if any shall be removed by tapping the boards and removing the same after 24 hours, curing the micro-concrete thoroughly for 14 Days etc. complete. The rate shall be inclusive of shuttering, strutting, curing etc. complete. (Excluding cost reinforcement). Make: Sunanda, Pidilite, Krishna Conchem, BASF etc.</p>	500.00	KG		

	<b>The Contractor has to carryout this work by part by part strengthening ceiling polymer work by giving proper support by propping the slab as per the direction of the Architect.</b>				
<b>6</b>	<b>TMT Steel</b> Providing and laying in position tested quality TMT Steel Fe 500 Reinforcement bars of required diameter and approved make including transporting the same to site, cutting, bending, tying at all heights and in all positions, providing concrete covers as required at any height etc complete.	1700.00	KG		
<b>7</b>	<b>TMT REINFORCEMENT RE_BARS</b> Providing & Fixing in position "TMT reinforcement Re-bars" of approved quality and diameter and fixing the same in position as per manufactureres specifications, including drilling holes of required diameter not exceeding 20mm upto the maimum depth of 160mm, injecting the grouting chemical HILTI HY 200R with help of approved dispenser before placing the TMT Reinforcement Bars in position complete as directed by Architect and as per manufacturer's specifications. (Rate inclusive of cost of TMT reinforcement of required length for grouting & the Chemical used.) Rebars, grouting chemical & dispenser to be HILTI make or equivalent, necessary test reports have to be obtained from the company from whom have purchased the chemicals & work should not be got carried out by the auhorised HILTI personal only.				
<b>7 a)</b>	<b>12mm</b>	200.00	NO		
<b>7b)</b>	<b>10mm</b>	200.00	NO		
<b>7c)</b>	<b>8mm</b>	200.00	NO		
<b>8</b>	<b>Props for 6th Floor Supports to RCC Members</b> Providing and erecting steel tubular props of required height up to 10'to 11', L head or flat head braced at centre and supporting a continuous 2" x 3" wooden runner, resting on wedge and block minimum capacity 3 Ton to support the structure provisionally during repair and jacketing etc. and maintaining them in position till required item etc. complete. The props are erected in perfect vertical in plumb taking / transferring the load equally / uniformly. The location of every prop should be one over another floor and it should not be eccentric.  The tightening of every prop should be uniform to all props to strain the building uniformly, removing the	75.00	NO		

	same as and when directed by structural engineer /Architect.				
9	<b>Props for 6th Floor Supports to slab</b> Refer Same Specification as mentioned in item no. I-8 (Wherever required as per the direction of the Architect Patra or plywood to be provided if Slab is more honeycomb in nature	370.00	SFT		
<b>B</b>	<b>DEMOLITION WORK</b>				
10	<b>Demolition of Existing Flooring /Wall tiles</b> Carefully dismantling and demolishing existing flooring tiles & Wall dado tiles including plastering etc. at all heights, levels and locations fixed in cement mortar or any other adhesive material using manual/mechanical means including necessary scaffolding, making the surface good and immediate carting away and disposal of unserviceable material/debris from Seventh floor to Ground floor as shown at site by the Architect to a place approved by Mumbai Municipal Corporation and as per direction of Architect. Rate to include stacking of all serviceable material at any floor as per the direction of Architect.	2,640.00	SFT		
11	<b>Demolition of Existing Skirting</b> Dismantling all type of existing skirting tiles of any thickness including plaster as per the direction of the Architect at any height and location including cleaning the surface and carting away unserviceable material / debris from Third Floor to Ground as shown at site by Architect and the same is to be carted away to a place approved by M.C.G.M. (Rate is including Scaffolding)	490.00	RFT		
12	<b>Demolition of Plaster</b> Dismantling existing all types of Internal wornout / loose plaster of any thickness and at any height and location including raking out joints of Brick work without causing dust/ nuisance and cleaning the surface and carting away unserviceable material / debris to a place as shown at site by Architect and the same is to be carted away to a place approved by M.C.G.M. (Rate is including Scaffolding)	7,665.00	SFT		
<b>C</b>	<b>CIVIL WORK</b>				
<b>C 1</b>	<b>Masonry work</b>				

<b>13</b>	<b>Plastering</b> Providing and laying Internal plaster of average 20 mm thk in Two coats in CM 1:4 to walls, ceiling at all heights including necessary scaffolding curing etc complete. Rate includes adding polypropylene fibre of approved quality as per propotion specified in the manufacturers specifications, chicken mesh, nails, curing etc complete as directed by the Architect.	5,750.00	SFT		
<b>14</b>	<b>Ceiling Plaster</b> Refer Same Specification as mentioned in item no. 13	1,915.00	SFT		
<b>C 2</b>	<b>Painting work</b>				
<b>15</b>	<b>Plastic Emulsion Paint</b> Providing and applying plastic emulsion paint to all internal walls with two coats of plastic emulsion paint of Asian Paints of approved shade and colour over coats of wall putty of Asian Paints or equivalent make and two coats of wall primer of Asian Paints or equivalent make. After scrapping the original surface and rubbing it with zero size sand paper and with one base coat of plasto fix primer, successively after drying each coat and finishing it. The rate shall include the coats of all materials, labour, scaffolding ,cleaning the glass planes, floor for paint drops after completion of painting works etc. Complete as directed by the Architect.	7,050.00	SFT		
<b>16</b>	<b>POP Punning</b> POP punning to the new wall/ plaster up to average thickness of 12 mm to proper level & plumb, including grooves etc to receive paint. The wall shall be cleaned, filled with putty to proper line and level. Complete as directed by the Architect.	7,050.00	SFT		
<b>17</b>	<b>Enamel Paint</b> Providing and applying one priming coat 2 & 3 coat or synthetic enamel paint over M.S. & other metal grills & wooden & ply surfaces including preparing the surface by thoroughly cleaning oil, grease, dirt and other foreign matter with wire brush fine steel wool and sand paper scaffolding etc. Complete as directed by the Architect. (Rate shall be inclusive of scaffolding)	1,230.00	SFT		
<b>C 3</b>	<b>TILING &amp; GRANITE WORK</b>				

18	<b>Vitrified Floor Tiles (600 x 600MM)</b> Providing and laying 600 x 600 x 10 mm thk. vitrified tiles as specified below conforming to I.S.15622-2006 with water absorbtion less than 0.08% for flooring of an approved, quality, make and pattern /design for flooring including cement mortar bedding of 25 mm thick in 1:4 proportion, cutting, leveling, jointing, filling the joints by neat cement slurry or approved colour grout, curing, finishing etc complete as directed by Architect. (Basic Tile Cost RS. 90/- Per SFT)	1,760.00	SFT		
19	<b>VitrifiedTileSkirtin(3"ht)</b> <b>Refer Same Specification as mentioned in item no. 18</b>	490.00	RFT		
20	<b>Vitrified Floor Tiles - Matt finish in Toilet</b> Providing and laying 600 x 600 x 10 mm thk. vitrified tiles as specified below conforming to I.S.15622-2006 with water absorbtion less than 0.08% for flooring of an approved, quality, make and pattern /design for flooring including cement mortar bedding of 25 mm thick in 1:4 proportion, cutting, leveling, jointing, filling the joints by neat cement slurry or approved colour grout, curing, finishing etc complete as directed by Architect.	160.00	SFT		
21	<b>Ceramic Wall Tiles at 7'.0" high in Toilet/Bath</b> Provide & Fixing 300 mm x 600mm Digital glazed Ceramic tiles with cement mortar (1:3) and joints to be filled with matching coloured pigment. Provide backing of 20mm thick cement sand (1:3) fixing in neat cement and complete as per direction of the Architect. (Contractor should understand the pattern & combination of tile pattern in the drawing or as per Architect's direction) (Basic CostConcept tile Rs.60/- Per Sq.FT.) Make: Kajaria / Somany / Simpolo/Johnson or equivalent as per sample approved by the Architect.	645.00	SFT		
22	<b>Ceramic Wall Tiles in Kitchen</b> Provide & Fixing 300 mm x 600mm Digital glazed Ceramic tiles with cement mortar (1:3) and joints to be filled with matching coloured pigment. Provide backing of 20mm thick cement sand (1:3) fixing in neat cement and complete as per direction of the Architect. (Contractor should understand the pattern & combination of tile pattern in the drawing or as per Architect direction) (Basic CostConcept tile Rs.60/- Per Sq.FT.) Make: Kajaria / Somany /	75.00	SFT		

	Simpolo/Johnson or equivalent as per sample approved by the Architect.				
23	<b>Granite Door Frame for Toilet Doors</b> Removing the existing wooden/stone frame and carting it away with any lift or lead and providing cement plaster in 1:3 and fix 19mm granite door frame in stepped form in neat cement float. Provide 2" high stepped Umra and side 7" wide 3" & 4" patti with moulding and dhar (edge) polish will make granite door frame which will be fixed with necessary brass washer, aeraldite, metal hold fast, etc. All exposed edges of granite to be half rounded. Complete as directed by the Architect (Basic Cost Of Granite Rs. 185/- Per Sq.FT.)	86.00	RFT		
24	<b>Granite Window frame for Toilet Windows</b> Providing & fixing 19mm thick Telephone Black Granite As approved quality, pattern & colour for flush/projected skirting, wall including metal washer & aeraldite, square cut top edge, or chamfered and moulding, top edge in cement mortar 1:3 cement float, machine cutting, leveling, jointing, filling the joints with neat cement or pigment mixed with cement, polishing, finishing, curing etc. Complete as directed by the Architect. (Basic Cost: Rs.185/sqft)	40.00	RFT		
25	<b>Granite Window/Balcony full ht sliding window frame</b> Providing & fixing 19mm thick Telephone Black Granite As approved quality, pattern & colour for flush/projected skirting, wall including metal washer & aeraldite, square cut top edge, or chamfered and moulding, top edge in cement mortar 1:3 cement float, machine cutting, leveling, jointing, filling the joints with neat cement or pigment mixed with cement, polishing, finishing, curing etc. Complete as directed by the Architect. (Basic Cost: Rs.185/sqft)	410.00	RFT		
26	<b>New Granite Platform in Kitchen</b> Breaking existing 'kitchen platform' and carting away the debris outside the premises to any lift & lead and providing and fixing in position new approved coloured granite platform, granite to be not less than 19 mm thick, fixed over 20mm thick marble vertical as well as horizontal with 1:1 sand cement screed or approved adhesive including cut out for SS sink of approved size, granite fascia approx 75-80 mm wide to be provided with edges rounded 12mm above the platform, including chasing the wall to fix the granite complete. Basic rate of granite including all taxes and transporting on site : Rs 200.00 Per SqFt. All Granite	9.00	RFT		

	edges to be rounded as directed by the Architect. providing and fixing in position 20mm thick marble shelf below sink to provided as directed by the Architect.				
<b>C 4</b>	<b>PLUMBING, DRAINAGE &amp; SANITARY FITTINGS WORK</b>				
	<b>Waterproofing work</b>				
<b>27</b>	<b>Waterproofing Work in Toilet</b> Removing existing waterproofing and Providing waterproofing treatment to Toilet slab including removing existing damaged waterproofing system & brick bat coba and clearing site with filling debris in gunny bags and the same to be carted away from the site as per the direction. Also making the slab surface thoroughly clean and treat the slab by laying waterproof material of approved make (Sunanda chemicals, Roff, Dr. Fixit Or Choksi chemicals) and as per Mfg. Specifications and provide 50 mm average thickness consisting of 12 mm thick layer in cement mortar 1:3 with water proofing compound at the rate of one K.G. per bag of cement as base constructing and keep water for 2 days for testing and only after confirming the waterproof treatment is properly done.	160.00	SFT		
<b>28</b>	<b>Waterproofing in Kitchen near Nahani trap</b> Removing existing waterproofing and Providing waterproofing treatment to Toilet slab including removing existing damaged waterproofing system & brick bat coba and clearing site with filling debris in gunny bags and the same to be carted away from the site as per the direction. Also making the slab surface thoroughly clean and treat the slab by laying waterproof material of approved make (Sunanda chemicals, Roff, Dr. Fixit Or Choksi chemicals) and as per Mfg. Specifications and provide 50 mm average thickness consisting of 12 mm thick layer in cement mortar 1:3 with water proofing compound at the rate of one K.G. per bag of cement as base constructing and keep water for 2 days for testing and only after confirming the waterproof treatment is properly done.	5.00	SFT		
	<b>Sanitary Fittings</b>				

29	<p><b>W.C. With All Accessories, Tap, Jet Spray Wall Hung Washbasin Set in Toilets</b></p> <p>Providing &amp; Fixing Wall Hung Wash basin set of Jaquar Continental CNS-WHT-811 make/ Hindustan (CEFFO STARWHITE)/ Parryware or equivalent make with following accessories as directed by the Architect.</p> <p>P/F Waste Coupling: ALD-709 Jaquar make or equivalent as approved by the Architect/Enginner.</p> <p>Pillar cock: CODE: CON-CHR-011KN Jaquar make or equivalent as approved by the Architect/Enginner.</p> <p>Bottle Trap: ALD-CHR-769L250X190 Jaquar make or equivalent as approved by the Architect.</p>	4.00	EACH		
30	<p><b>Wash Basin Set with mixer</b></p> <p>Providing &amp; Fixing Wall Hung Wash basin set of Jaquar Continental CNS-WHT-811 make/ Hindustan (CEFFO STARWHITE)/ Parryware or equivalent make with following accessories as directed by the Architect.</p> <p>P/F Waste Coupling: ALD-709 Jaquar make or equivalent as approved by the Architect.</p> <p>Pillar cock: CODE: CON-CHR-011KN Jaquar make or equivalent as approved by the Architect.</p> <p>Bottle Trap: ALD-CHR-769L250X190 Jaquar make or equivalent as approved by the Architect.</p> <p>Angle cock: CON-CHR-053KN Jaquar make or equivalent as approved by the Architect.</p>	5.00	EACH		
31	<p><b>Tap Set (3 in 1 Mixer, Stop Cock, Angle Cock, Shower, Telephone Shower)</b></p> <p>Providing and fixing Tap set of Jaquar Continental make with the following specifications Mixer (3 In 1) CON-281KN, Hand shower: HSH-1737, Flexi Tube: SHA 571, Wall Bracket: SHA-477, Over Head Shower: OHS-1989, Wall Mounted Shower Arm: SHA-477, Stop cock Body: CON-053KN with Flange, Bib Cock : CON-037KN. Complete as directed by the Architect.</p>	4.00	SET		
32	<p><b>Stainless Steel Sink including plumbing &amp; Drainage</b></p> <p>Providing and fixing Stainless Steel Sink of Nirali (glossy) make having model no. Orra large 18" x 24". Provide and fix sink cock and bottle trap of Jaquar or equivalent make with the following specifications CON-CHR-347KNM and ALD-CHR-769L250X190 respectively. The rate is inclusive of plumbing and drainage work. Complete as directed by the Architect.</p>	1.00	JOB		
	<b>Accessories</b>				



33	<b>Mirror above wash Basin</b> Providing 18" x 36" Mirror with 2" x 1" wooden frame with conceal hook 2 nos. Provide and fix on the wall above washbasin 6mm thk mirror with 4 S.S. Studs. Complete as directed by the Architect.	5.00	EACH		
34	<b>Soap dish</b> Providing and fixing Soap dish of Jaquar brand model no. ACN-1131N with all the necessary accessories. Complete as directed by the Architect.	4.00	EACH		
35	<b>Double coat hook</b> Providing and fixing Double Coat hook of Jaquar brand model no. ACN-1161N with all the necessary accessories. Complete as directed by the Architect.	4.00	EACH		
36	<b>Toilet Roll Holder with flap</b> Providing and fixing Toilet Roll Holder with Flap of Jaquar brand model no. ACN-1153N with all the necessary accessories. Complete as directed by the Architect.	4.00	EACH		
	<b>Plumbing and Drainage work</b>				
37	<b>Chilli Nahani Trap</b> Providing and fixing Chili nahani trap as approved by the Architect.	5.00	EACH		
38	<b>Removing existing sanitary, plumbing, Taps etc.</b> Removing existing Drainage and Plumbing lines carefully without damaging and internal connection of the flat. Complete as directed by the Architect.	4.00	JOB		
39	<b>Plumbing Piping Work</b> Providing and fixing 15mm (1/2")Dia Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, fixing the pipe with clamps at 1.00 m spacing. This includes joining of pipes & fittings with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of Architect. Concealed work, including cutting chases and making good the walls etc.. (AstraL/Ashirwad/ Oriplast / Supreme brand) with all fittings as per instructions of Architect.	4.00	JOB		
40	<b>Drainage Work (75mm / 100mm /32mm)</b> Providing & fixing PVC SWR Pipe line 6kg/cm2 with necessary essentials to the drainage and water water outlet in the sunken and external area, rain water pipes	4.00	JOB		

	with proper slope and adhesives complete with necessary fittings. Complete as directed by the Architect.				
<b>D</b>	<b>MISCELLANEOUS WORK</b>				
<b>41</b>	<b>Shutters Below Kitchen Platform (9'.0" x 2'.8")</b> Providing & Fixing 19mm BWR Ply as per 3 steel Drawer in 3 compartment and 2 door one compartment below sink. The internal area finish with 0.8mm thk laminate and exterior area finish with 1mm laminate in 2 colours including thickness of door. Provide and fix 2" x 1" T. Wood frame with Laminate finish. Provide & fix all the necessary Brass Hardware, Handle, Hinges, etc. Complete as directed by the Architect.	24.00	SFT		
<b>42</b>	<b>Steel Trolley below Granite Platform</b> Providing 3 drawer unit module in 3 different compartment with top, middle, bottom 4", 6", 8" high S.S. 304 Grade drawer 2'.0" wide, 2'.3" depth with steel basket slide with telescopic channel as per design and direction of Architect. as per above. Complete as directed by the Architect.	24.00	SFT		
<b>43</b>	<b>Aluminium Window (3 Track)</b> Providing and fixing in position three track aluminum window of extruded modular and anodized aluminum sections of approved make and of size 61.85 mm x 45.5 mm x 1.3 mm thk (wt 1.055 kg/Rm) for bottom, 61.85 mm x 31.75 mm x 1.3 mm thk. (wt 0.659 kg / Rm) for top & sides, mounted on anodized aluminum rectangular frame of size 63mm x 38mm x 2.0mm (1.054). The shutter comprising of bearing bottom and top of size 40mm x 18 mm x 1.25 mm thk (wt. 0.417 Kg/Rm) Interlocking section of size 40mm x 26,7 mm x 1.10 mm thk. (Wt. 0469 kg./Rm) and hand sides of 40mm x 18mm x 1.25 mm thk (wt. 0.417kg/Rm) with	345.00	SFT		
<b>44</b>	<b>Aluminium Window (4 Track) - Full Ht</b> Refer Same Specification as mentioned in item no. 43	227.00	SFT		
<b>45</b>	<b>Aluminium Window (2 Track)</b> Refer Same Specification as mentioned in item no. 43	85.00	SFT		
<b>46</b>	<b>New Louvered Windows</b> Providing window made of openable Louvered Blades & space for Exhaust Fan with necessary Aluminium 16 guage 2" x 1" pipe frame, Ivory Powder Coated finish & 4mm Thk Frosted/Bajri	27.00	SFT		

	Glass. Complete as per design and direction of the Architect.				
47	<b>Gypsum Falseceiling Work (Including Cove )</b> Providing, fabrication and fixing in position of false ceiling at a height of 9'.6"/ 9'.0" from floor (or the height will be decided on spot as per the site conditions as directed by the Architect/ Bank's Engineer) by fixing 12 mm Th. Gypsum Board sheets on frame work of GI sheet section. The main runners of 22 gauge GI sheet and cross runners of 24 gauge GI sheet must be framed to form a mesh of 600 x 600 mm c/c. The Gypsum Board must be fixed to the GI frame and joints must be properly filled in with POP paste and paper tape, supplied by the manufacturer, to get a levelled smooth ceiling, including acrylic paint three or more coats in 2 to 3 colours as approved and directed by the Architect/ Bank's Engineer. Recessing of the Gypsum Board for light fixtures must be done alongwith extra frame work of GI sheet section to hold the concealed light fixtures. The rate is inclusive of Cove Lighting and no separate payment will be made for the verticals for cove lighting. Complete as per design and direction of the Architect/ Bank's Engineer.	2,500.00	SFT		
<b>E</b>	<b>ELECTRICAL WORK</b>				
48	<b>LIGHT POINT</b> Providing & Fixing of Light Point Wiring in ISI mark <b>POLYCAB make FRLS 1.5SQMM x 2 wires</b> <b>2.5SQmm Circuit wiring with Precession make MMS</b> grade Pipes etc complete work from SB to Light points ends with roma switches & accessories.				
48 a	Light Points wiring.....	40.00	Pts.		
48 b	2WAY POINTS...	10.00	Pts.		
48 c	Fan points with ROD HOOK CYCLE & REGULATOR etc .... Living & Dining 4, Balcony 1, Bed rooms 3 no, Kitchen 2 no. Servants room 1 no.	8.00	Pts.		
48 d	do as above but for Exhaust fan points with fan hook etc ....	5.00	Pts.		
48 e	Do as above but for secondary light pts. ( from first pt to second )	10.00	Pts.		
49	P & F of 2.5Sqmm X 2 wires with earth for with 5Amps Switch Socket etc from main DB to switch boards.	20.00	Pts.		

<b>50</b>	P & F of 4Sqmm X 2 wires with earth with 5/15Amps Switch socket pate for AC wiring & Kitchen appliance & geyser from main DB to each power points....	20.00	Pts.		
<b>51</b>	P & F of D link make cat 6 Wires from Router to work station & landline for voice....	6.00	Pts.		
<b>52</b>	Main distribution Board P & F of LEGRAND make 12Way TPN DB with 63Amps FP MCB & 63Amps FP ELCB with 36SP MCB....	1.00	Nos.		
<b>53</b>	P&Fof TV Cable wiring. P & F OF Polycab mak RG 6 wires laid in precesion make pipes from Mains to premises & premises to each room	5.00	Pts.		
<b>54</b>	P & F of Philips make 22 W Led Tube Putty	35.00	Nos.		
<b>55</b>	P & F of Racold make 15Lit 6.5 kw Geyser.	4.00	Nos.		
<b>56</b>	P & F Crompton make 1200mm Ceilling fan with regulator.	8.00	Nos.		
<b>57</b>	P & F of Crompton 250mm Exhaust Fan with louvers.	5.00	Nos.		
	NET TOTAL (Exclusive of Taxes)				