

SCHEDULE OF QUANTITIES FOR CIVIL WORK AT CO'S GUEST HOUSE FLAT NO. 13-B, SAGAR APARTMENT, NEW DELHI.

S.No	Particulars	Quantity	Unit	Rate	Amount
	CIVIL WORK				
1	Dismantalling of existing steel window, wooden window, m.s windows, plaster where ever required etc. complete and dispose off the debris from the site.	1.00	Nos.		
2	12MM plaster cement sand 1:6 in walls (1 cement : 6 fine sand) in the balcony parapet wall with mosaic finish matching with the existing finish quality shade and pattern. Complete with all.	402.21	SQ.FT.		
3	Constructing 115 mm thk. Brick wall in 1:6 cement mortar. Brick used shall be of best quality kiln burnt, having sharp edges & giving clear ringing sound when struck against each other. The rate shall be inclusive of any scaffolding required, curing etc., complete. (Room No.2)	58.00	SQ.FT.		
4	Providing and fixing Fiber sheet shed with M.S. frame of 1 1/2" x 1 1/2" m.s. hollow tube with 2'-0" x 2'-0" c/c with proper welding of hollow pipes below the fiber sheet with required nut and bolt complete with all the required fitting and fixture. complete with all or as per instruction by the insurance company.	80.00	SQ.FT.		
5	Providing & Fixing UPVC window frame 38mm thick shutter three track three panel sliding window with two glazed toughened glass of 6.00 mm thick & one wire mesh panels with aluminium channel for roller track , wood pile, nylon rollers with ss 304 body, with zinc alloy powder coated handle on every glazed panel along with multi point locking system. (Drawing Room Window)	80.00	SQ.FT.		
	After fixing frame the gap between frame and adjacent finished wall shall be filled with weather proof silicon sealant.				
	PAINTING WORK				
6	Applying three or more coats of Acrylic Emulsion Paint (ASIAN) emulsion shine of approved shade including making of ground, rubbing, filling of putty base preparation with BIRLA/ JK Putty, applying a coat of cement primer, complete. In case where the surface has been earlier white/colour washed, the old white/colour wash shall be entirely removed and surface broomed/scrapped down before preparing the surface for applying paint as described above. Rates include cleaning of splashes, stains on floor, window panes etc and scaffolding, if required and for all heights.	4482.26	SQ.FT.		

7	Enamel paint : Providing & applying 1st quality of paint of approved make , quality & shade . The rate shall includes scrapping levelling & preparing the surface with primer quote. (Asian / Berger)	1.00	LUMSUM		
8	Providing & Fixing green construction safety net as per the site requirement during the dismantalling of all the windows to protect or safe guard the people working below on ground floor and remove the debris from the site.	1.00	LUMSUM		
	AMOUNT				
	GST				
	AMOUNT INCL GST				